

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐
(highlight changes)

APPLICATION FOR PERMIT TO DRILL				5. MINERAL LEASE NO: ML-47045	6. SURFACE: State
1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEEN <input type="checkbox"/>				7. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER _____ SINGLE ZONE <input type="checkbox"/> MULTIPLE ZONE <input checked="" type="checkbox"/>				8. UNIT or CA AGREEMENT NAME:	
2. NAME OF OPERATOR: EOG Resources, Inc.				9. WELL NAME and NUMBER: East Chapita 60-16	
3. ADDRESS OF OPERATOR: 1060 East Highway 40 CITY Vernal STATE UT ZIP 84078			PHONE NUMBER: (435) 781-9111	10. FIELD AND POOL, OR WILDCAT: Natural Buttes/Mesaverd/Wasatch	
4. LOCATION OF WELL (FOOTAGES) 642 982x 4433 493Y 40.041444 AT SURFACE: 655 FNL 625 FEL (NENE) 40.041408 LAT 109.324756 LON AT PROPOSED PRODUCING ZONE: Same -109.324017				11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENE 16 9S 23E S	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: 55.3 Miles Southeast of Ouray, Utah				12. COUNTY: Uintah	13. STATE: UTAH
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 625		16. NUMBER OF ACRES IN LEASE: 640		17. NUMBER OF ACRES ASSIGNED TO THIS WELL: 40	
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) 2550		19. PROPOSED DEPTH: 9,070		20. BOND DESCRIPTION: NM 2308	
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): 4965 GR		22. APPROXIMATE DATE WORK WILL START:		23. ESTIMATED DURATION: 45 DAYS	

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT			SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT
17-1/2	13-3/8	H-40	48#	45	See Attached Eight Point Plan
12-1/4	9-5/8	J-55	36#	2,300	See Attached Eight Point Plan
7-7/8	4-1/2	N-80	11.6#	9,070	See Attached Eight Point Plan

ATTACHMENTS

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:

- | | |
|--|--|
| <input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER
<input checked="" type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER | <input checked="" type="checkbox"/> COMPLETE DRILLING PLAN
<input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER |
|--|--|

NAME (PLEASE PRINT) **Kaylene R. Gardner**

TITLE **Sr. Regulatory Assistant**

SIGNATURE 

DATE **3/15/2007**

(This space for State use only)

API NUMBER ASSIGNED: **43047-39150**

**Approved by the
Utah Division of
Oil, Gas and Mining**

APPROVAL:

Date: **04-24-07**

By: 

(See Instructions on Reverse Side)

RECEIVED

MAR 19 2007

DIV. OF OIL, GAS & MINING

LATITUDE = (NAD 83) 40°02'29.07" (40.041408)
 LONGITUDE = 109°19'29.12" (109.324756)
 LATITUDE = (NAD 27) 40°02'29.16" (40.041433)
 LONGITUDE = 109°19'26.68" (109.324078)

STATE OF UTAH)

) ss

COUNTY OF UINTAH)

VERIFICATION

Kaylene R. Gardner, of lawful age, being first duly sworn upon oath, deposes and says:

She is the Sr. Regulatory Assistant of EOG Resources, Inc., of Vernal, Utah. EOG Resources, Inc. is the operator of the following described well:


EAST CHAPITA 60-16
655' FNL – 625' FEL (NENE)
SECTION 16, T9S, R23E
UINTAH COUNTY, UTAH

EOG Resources, Inc., is the only owner in the well and/or of all contiguous oil and gas leases or drilling units overlying the pool.

On the 16th day of March, 2007 she placed in the United States mail, with postage prepaid, a copy of the attached Application for Commingling in one wellbore for the subject well.


Said envelope which contained these instruments was addressed to the Utah Division of Oil, Gas & Mining.

Further affiant saith not.




Kaylene R. Gardner
Sr. Regulatory Assistant


Subscribed and sworn before me this 16th day of March, 2007.




My Commission Expires:

4-15-2008



Notary Public


R 23 E



○ EAST CHAPITA 60-16

Scale: 1"=1000'

0 1/4 1/2 Mile

 **eog resources**

Denver Division

EXHIBIT "A"

EAST CHAPITA 60-16
Commingling Application
Uintah County, Utah

Scale:
1"=1000'

D:\utah\Commingling\page_EC60-16_commingling.dwg
WELL

Author

TLM

Mar 06, 2007 -
10:20am

EIGHT POINT PLAN

EAST CHAPITA 60-16
NE/NE, SEC. 16, T9S, R23E, S.L.B.&M..
UINTAH COUNTY, UTAH

1. & 2. ESTIMATED TOPS & ANTICIPATED OIL, GAS, & WATER ZONES:

FORMATION	TVD-RKB (ft)	Objective	Lithology	
Green River	1,716		Shale	
Wasatch	4,649	Primary	Sandstone	Gas
Chapita Wells	5,224	Primary	Sandstone	Gas
Buck Canyon	5,915	Primary	Sandstone	Gas
North Horn	6,478	Primary	Sandstone	Gas
KMV Price River	6,826	Primary	Sandstone	Gas
KMV Price River Middle	7,621	Primary	Sandstone	Gas
KMV Price River Lower	8,479	Primary	Sandstone	Gas
Sego	8,867		Sandstone	
TD	9,070			

Estimated TD: **9,070' or 200'± below Sego top**

Anticipated BHP: 4,952 Psig

1. Fresh Waters may exist in the upper, approximately 1,000 ft ± of the Green River Formation, with top at about 2,000 ft ±.
2. Cement isolation is installed to surface of the well isolating all zones by cement.

3. PRESSURE CONTROL EQUIPMENT:

Production Hole – 5000 Psig
BOP schematic diagrams attached.

4. CASING PROGRAM:

CASING	Hole Size	Length	Size	WEIGHT	Grade	Thread	Rating Collapse	Factor Burst	Tensile
Conductor	17 ½"	0 – 45'	13 ⅜"	48.0#	H-40	STC	770 PSI	1730 PSI	322,000#
Surface	12 ¼"	0 – 2,300' KB±	9-⅝"	36.0#	J-55	STC	2020 PSI	3520 Psi	394,000#
Production	7-7/8"	Surface – TD	4-½"	11.6#	N-80	LTC	6350 PSI	7780 Psi	223,000#

Note: 12-¼" surface hole will be drilled to a total depth of 200'± below the base of the Green River lost circulation zone and cased w/9-⅝" as shown to that depth. Drilled depth may be shallower or deeper than the 2300' shown above depending on the actual depth of the loss zone.

All casing will be new or inspected.

EIGHT POINT PLAN
EAST CHAPITA 60-16
NE/NE, SEC. 16, T9S, R23E, S.L.B.&M..
UINTAH COUNTY, UTAH

5. Float Equipment:

Surface Hole Procedure (0' - 2300'±)

Guide Shoe

Insert Float Collar (PDC drillable)

Centralizers: 1-5' above shoe, top of jts. #2 and #3 then every 5th joint to surface. (15 total)

Production Hole Procedure (2300'± - TD):

Float shoe, 1 joint casing, float collar and balance of casing to surface. 4-½", 11.6#, N-80 or equivalent marker collars or short casing joints to be placed at top of Price River and 400' above top of Wasatch. Centralizers to be placed 5' above shoe on joint #1, top of joint #2, and every 2nd joint to 400' above Wasatch Island top. Thread lock float shoe, top and bottom of float collar, and top of 2nd joint.

6. MUD PROGRAM

Surface Hole Procedure (Surface - 2300'±):

Air/air mist or aerated water.

Production Hole Procedure (2300'± - TD): Anticipated mud weight 9.5 – 10.5 ppg depending on actual wellbore conditions encountered while drilling.

2300'± - TD A closed mud system will be utilized. A bentonite gelled water mud system will be used to control viscosity w/PHPA polymer used for supplemental viscosity and clay encapsulation/inhibition. Water loss will be maintained at <15cc's using white starch or PAC. Bactericides will be used as needed. Anticipated pH will range from 9.0-10.0. Mud weight will be adjusted as necessary for well control. Deflocculants/thinners will be used as necessary to maintain mud quality. LCM sweeps will be utilized as necessary to control lost circulation and mud loss. CO2 contamination, if encountered, will be treated with lime and gypsum.

7. VARIANCE REQUESTS:

Reference: Onshore Oil and Gas Order No. 2 – Item E: Special Drilling Operations

EOG Resources, Inc. requests a variance to regulations requiring the blooie line to be 100' in length. Due to reduce location excavation, the blooie line will be approximately 75' in length

EIGHT POINT PLAN

EAST CHAPITA 60-16
NE/NE, SEC. 16, T9S, R23E, S.L.B.&M..
UINTAH COUNTY, UTAH

8. EVALUATION PROGRAM:

Logs: Mud log from base of surface casing to TD.
Cased-hole Logs: Cased-hole logs will be run in lieu of open-hole logs consisting of the following:
Cement Bond / Casing Collar Locator and Pulsed Neutron

9. CEMENT PROGRAM:

Surface Hole Procedure (Surface - 2300'±):

Lead: **185 sks** Class "G" cement with 16% Gel, 10 #/sx Gilsonite, 3% Salt, 2% CaCl₂, 3 lb/sx GR3 ¼ #/sx Flocele mixed at 11 ppg, 3.82 ft³/sk. yield, 23 gps water.

Tail: **207 sks** Class "G" cement with 2% CaCl₂, ¼#/sk Flocele mixed at 15.6 ppg, 1.18 ft³/sk., 5.2 gps water.

Top Out: As necessary with Class "G" cement with 2% CaCl₂, ¼#/sk Flocele mixed at 15.6 ppg, 1.18 ft³/sk., 5.2 gps water.

Note: Cement volumes will be calculated to bring lead cement to surface and tail cement to 500' above the casing shoe.

Production Hole Procedure (2300'± - TD)

Lead: **135 sks:** Hi-Lift "G" w/12% D20 (Bentonite), 1% D79 (Extender), 5% D44 (Salt), 0.2% D46 (Antifoam), 0.25% D112 (Fluid Loss Additive), 0.25 pps D29 (cello flakes) mixed at 11.0 ppg, 3.91 ft³/sk., 24.5 gps water.

Tail: **870 sks:** 50:50 Poz "G" w/ 2% D20 (Bentonite), 0.1% D46 (Antifoam), 0.075% D13 (Retarder), 0.2% D167 (Fluid Loss Additive), 0.2% D65 (Dispersant), mixed at 14.1 ppg, 1.28 ft³/sk., 5.9gps water.

Note: The above number of sacks is based on gauge-hole calculation.
Lead volume to be calculated to bring cement to 200'± above 9-5/8" casing shoe.
Tail volume to be calculated to bring cement to 400'± above top of Wasatch.

Final Cement volumes will be based upon gauge-hole plus 45% excess.

EIGHT POINT PLAN

EAST CHAPITA 60-16
NE/NE, SEC. 16, T9S, R23E, S.L.B.&M..
UINTAH COUNTY, UTAH

10. ABNORMAL CONDITIONS:

Surface Hole (Surface - 2300'±):

Lost circulation

Production Hole (2300'± - TD):

Sloughing shales, lost circulation and key seat development are possible in the Wasatch Formation.

11. STANDARD REQUIRED EQUIPMENT:

- A. Choke Manifold
- B. Upper and Lower Kelly Cock
- C. Stabbing Valve
- D. Visual Mud Monitoring


12. HAZARDOUS CHEMICALS:

No chemicals subject to reporting under SARA title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.

(Attachment: BOP Schematic Diagram)


**EOG RESOURCES 11" 5,000 PSI W.P. BOP
CONFIGURATION**

PAGE 1 OF 2



EOG RESOURCES CHOKE MANIFOLD CONFIGURATION W/ 5,000 PSI WP VALVES

PAGE 2 OF 2



Testing Procedure:

1. BOP will be tested with a professional tester to conform to Onshore Order #2.
2. Blind and Pipe rams will be tested to rated working pressure, 5,000 psi.
3. Annular Preventer will be tested to 50% working pressure, 2,500 psi.
Casing will be tested to 0.22 psi / ft. or 1,500 psi. Not to exceed 70% of burst strength, **whichever is greater.**
4. All lines subject to well pressure will be tested to the same pressure as blind and pipe rams.
5. All BOPE specifications and configurations will meet Onshore Order #2 requirements.



***EAST CHAPITA 60-16
NENE, Section 16, T9S, R23E
Uintah County, Utah***

SURFACE USE PLAN

NOTIFICATION REQUIREMENTS

- | | |
|----------------------------------|--|
| Location Construction: | Forty-eight (48) hours prior to construction of location and access roads. |
| Location Completion: | Prior to moving on the drilling rig. |
| Spud Notice: | At least twenty-four (24) hours prior to spudding the well. |
| Casing String and Cementing: | Twenty-four (24) hours prior to running casing and cementing all casing strings. |
| BOP and related Equipment Tests: | Twenty-four (24) hours prior to running casing and tests. |
| First Production Notice: | Within five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days. |

The well pad is approximately 325 feet long with a 246-foot width, containing 1.84 acres more or less. The well access road is approximately 1848 feet long with a 30-foot right-of-way, disturbing approximately 1.27 acres. New surface disturbance associated with access road and the well pad is estimated to be approximately 3.11 acres. The pipeline is approximately 2418 feet long with a 40-foot right-of-way, disturbing approximately 2.22 acres.

1. EXISTING ROADS:

- A. See attached Wellsite Plats showing directional reference stakes on location, and attached TOPO Map "B" showing access to location from existing roads.
- B. The proposed well site is located approximately 55.3 miles south of Myton, Utah – See attached TOPO Map "A".
- C. Refer to attached Topographic Map "A" showing labeled access route to location.
- D. Existing roads will be maintained and repaired as necessary.

2. PLANNED ACCESS ROAD:

- A. The access road will be approximately 1848' in length. See attached Topo Map "B".
- B. The access road has a 30 foot ROW w/18 foot running surface.
- C. Maximum grade of the new access road will be 8 percent.
- D. No turnouts will be required.
- E. Road drainage crossings shall be of the typical dry creek drainage crossing type.
- F. No culverts, bridges, or major cuts and fills will be required.
- G. The access road will be dirt surface.
- H. No gates, cattleguards, or fences will be required or encountered.

New or reconstructed roads will be centerlined – flagged at time of location staking.

Road drainage crossings shall be of the typical dry creek drainage crossing type. Crossings shall be designed so they will not cause siltation or accumulation or debris in the drainage crossings nor shall the drainages be blocked by the roadbed. Erosion of drainage ditches by run off water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading shall not be allowed during muddy conditions. Should mud holes develop, they shall be filled in and detours around then avoided.

As operator, EOG Resources, Inc. shall be responsible for all maintenance on cattleguards, or gates associated with this oil and/or gas operation.

Traveling off the 30 foot right-of-way will not be allowed. The access road and associated drainage structures will be constructed and maintained in accordance with road guidelines contained in the joint BLM/USFS publication: Surface Operating Standards for Oil and Gas Exploration and Development, Third Edition, and/or BLM Manual Section 9113 concerning road construction standards on projects subject to federal jurisdiction. During the drilling and production phase of operations, the road surface and shoulders will be kept in a safe and useable condition and drainage ditches and culverts will be kept clear and free flowing.

3. LOCATION OF EXISTING WELLS WITHIN A ONE-MILE RADIUS:

See attached TOPO map "C" for the location of wells within a one-mile radius.

4. LOCATION OF EXISTING AND/OR PROPOSED PRODUCTION FACILITIES:

A. On Well Pad

1. Production facilities will be set on location if the well is successfully completed for production. Facilities will consist of wellhead valves, combo separator-dehy unit with meter, two (2) 400 BBL vertical tanks and attaching piping.
2. Gas gathering lines – A 4" gathering line will be buried from dehy to the edge of the location.

B. Off Well Pad

1. Proposed location of attendant off pad flowlines shall be flagged prior to archaeological clearance.
2. The length of the new proposed pipeline is 2418' x 40', containing 2.22 acre more or less. The proposed pipeline leaves the western edge of the well pad turning and proceeding in an southerly direction for an approximate distance of 2418'. The pipe will tie into an existing pipeline in the SWNE of Section 16, T9S, R23E (ML 47045). Pipe will be 4" NOM, 0.156 wall, Grade X42, Zap-Lok, electric weld with a 35 mil X-Tru coating.
3. Proposed pipeline will be a 4" OD steel, welded line laid on the surface
4. Protective measures and devices for livestock and wildlife will be taken and /or installed where required.

If storage facilities/tank batteries are constructed on this lease, the facility/battery or the well pad shall be surrounded by a containment dike of sufficient capacity to contain, at a minimum, the entire contents of the largest tank within the facility/battery, unless more stringent protective requirements are deemed necessary by the authorized officer.

All permanent (on site for six months or longer) structures constructed or installed (including pumping units) will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within 6 months of installation. **All existing facilities will be painted with Carlsbad Canyon.** Facilities required to comply with O.S.H.A. (Occupational Safety and Health Act) will be excluded.

5. LOCATION AND TYPE OF WATER SUPPLY:

- A. Water supply will be from Ouray Municipal Water Plant at Ouray, Utah, and/ or Target Trucking Inc.'s water source in the SW/SW. Sec 35, T9S, R22E Uintah County, Utah (State Water Right # 49-1501, and/or Bonanza Power Plant water source in Sec 26, T8S, R23E Uintah County, UT (State Water Right # 49-225(A31368)). Water will be hauled by a licensed trucking company.
- B. Water will be hauled by a licensed trucking company.
- C. No water well will be drilled on lease.

6. SOURCE OF CONSTRUCTION MATERIALS:

- A. All construction material for this location and access road will be of native borrow and soil accumulated during the construction of the location.
- B. No mineral materials will be required.

7. METHODS OF HANDLING WASTE DISPOSAL:

A. METHODS AND LOCATION

- 1. Cuttings will be confined in the reserve pit.
- 2. A portable toilet will be provided for human waste during the drilling and completion of the well. Disposal will be at the Vernal sewage disposal plant.
- 3. Burning will not be allowed. Trash and other waste material will be contained in a wire mesh cage and disposed of at the Uintah County Landfill.
- 4. Produced wastewater will be confined to a lined pit or storage tank for a period not to exceed 90 days after initial production. After the 90 day period, the produced water will be contained in a tank on location and then disposed of at one of the following three locations: Natural Buttes Unit 21-20B SWD, Ace Disposal, or EOG Resources, Inc. drilling operations (Chapita Wells Unit, Natural Buttes Unit & Stagecoach Unit).
- 5. All chemicals will be disposed of at an authorized disposal site. Drip pans and absorbent pads will be used on the drilling rig to avoid leakage of oil to the pit.

- B. Water from drilling fluids and recovered during testing operations will be disposed of by either evaporating in the reserve pit or by removed and disposed of at an authorized disposal site. Introduction of well bore hydrocarbons to the reserve pit will be avoided by flaring them off in the flare pit at the time of recovery.

The reserve pit will be constructed so as not to leak, break, or allow discharge. If the reserve pit requires padding prior to lining (due to rocky conditions) felt padding will be used.

The reserve pit shall be lined with felt and a 16 millimeter plastic liner.

EOG Resources, Inc. maintains a file, per 29 CFR 1910.1200 (g) containing current Material Safety Data Sheets (MSDS) for all chemicals, compounds, and/or substances which are used during the course of construction, drilling, completion, and production operations for this project. Hazardous materials (substances) which may be found at the site may include drilling mud and cementing products which are primarily inhalation hazards, fuels (flammable and/or combustible), materials that may be necessary for well completion/ stimulation activities such as flammable or combustible substances and acids/gels (corrosives). The opportunity for Superfund Amendments and Reauthorization Act (SARA) listed Extremely Hazardous Substances (EHS) at the site is generally limited to proprietary treating chemicals. All hazardous and EHS and commercial preparations will be handled in an appropriate manner to minimize the potential for leaks or spills to the environment.

8. ANCILLARY FACILITIES:

None anticipated.

9. WELL SITE LAYOUT:

- A. Refer to attached well site plat for related topography cuts and fills and cross sections.
- B. Refer to attached well site plat for rig layout and soil material stockpile location as approved on On-site.
- C. Refer to attached well site plat for rig orientation, parking areas, and access road.

The reserve pit will be located on the west corner of the location. The flare pit will be located on the north side of the location, a minimum of 100 feet from the well head and 30 feet from the reserve pit fence.

The stockpiled pit topsoil will be stored separate from the location topsoil east of Corner #5. The stockpiled location topsoil will be stored between corner #2 and #8. Upon completion of construction, the stockpiled topsoil from the location will be broadcast seeded with the approved seed mixture from this location and then walked down with a Caterpillar tractor.

Access to the well pad will be from the east.

FENCING REQUIREMENTS:

All pits will be fenced according to the following minimum standards:

- A. Thirty-nine inch net wire shall be used with at least one strand of barbed wire on top of the net wire. (Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.)
- B. The net wire shall be no more than 2 inches above the ground. The barbed wire strand shall be 3 inches above the net wire. Total height of the fence shall be at least 42 inches.
- C. Corner posts shall be cemented and/or braced in such a manner as to keep the fence tight at all times.
- D. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distances between any two posts shall be no greater than 16 feet.
- E. All wire shall be stretched by using a stretching device before it is attached to the corner posts.

The reserve pit fencing will be on the three sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until clean-up.

Each existing fence to be crossed by the access road shall be braced and tied off before cutting so as to prevent slacking of the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and, upon completion of construction, the fence shall be repaired to BLM or SMA specifications. A cattleguard with an adjacent 16 foot gate shall be installed in any fence where a road is regularly traveled. If the well is a producer, the cattleguards (shall/shall not) be permanently counted on concrete bases. Prior to crossing any fence located on Federal land, or any fence between Federal land and private land, the operator will contact the BLM, who will in turn contact the grazing permittee or owner of said fence and offer him/her the opportunity to be present when the fence is cut in order to satisfy himself/herself that the fence is adequately braced and tied off.

10. PLANS FOR RECLAMATION OF THE SURFACE:

A. Producing Location

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, materials, trash, and junk not required for production.

Immediately upon well completion, any hydrocarbons on the pit shall be removed.

If a plastic nylon reinforced liner is used, it shall be torn and perforated before backfilling of the reserve pit.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The stockpiled pit topsoil will then be spread over the pit area and broadcast seeded with the prescribed seed mixture for this location. The seeded area will then be walked down with a cat.

B. Dry Hole/Abandoned Location

At such time as the well is plugged and abandoned, the operator will submit a subsequent report of abandonment and the UDOGM will attach the appropriated surface rehabilitation conditions of approval.

11. SURFACE OWNERSHIP:

Surface ownership of the proposed well site, access road, and pipeline route is as follows:

State of Utah

12. OTHER INFORMATION:

A. EOG Resources, Inc. will inform all persons in the area who are associated with this project that they are subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, the operator will immediately stop work that might further disturb such materials, and contact the Authorized Officer. Within five working days the Authorized Officer will inform the operator as to:

- Whether the materials appear eligible for the National Register of Historic Places;
- The mitigation measures the operator will likely have to undertake before the site can be used.
- A time frame for the Authorized Officer to complete an expedited review under 36 CFR 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the Authorized Officer are correct and that mitigation is appropriate.

If the operator wished, at any time, to relocate activities to avoid the expense of mitigation and/or the delays associated with this process, the Authorized Officer will assume responsibility for whatever recordation and stabilization of the exposed materials that may be required. Otherwise, the operator will be responsible for mitigation costs. The Authorized Officer will provide technical and procedural guidelines for the conduct of mitigation. Upon verification from the Authorized Officer that required mitigation has been completed, the operator will then be allowed to resume construction.

B. As operator, EOG Resources, Inc. will control noxious weeds along Right-of-Ways for roads, pipelines, well sites, or other applicable facilities.

- C. The drilling rig and ancillary equipment will be removed from the location prior to commencement of completion operations. Completion operations will be conducted utilizing a completion/workover rig.
- D. Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on Utah State lands after the conclusion of drilling operations or at any other time without Utah State authorization. However, if Utah State authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities. (Utah State does not seek to compete with private industry. There are commercial facilities available for stacking and storing drilling rigs.)

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice of Lessees. The operator is fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Construction activity will not be conducted using frozen or saturated soils material or during periods when watershed damage is likely to occur.

If the existing access road, proposed access road, and proposed pad are dry during construction, drilling, and completion activities, water will be applied to help facilitate compaction during construction and to minimize soil loss as a result of wind erosion.

13. LESSEE OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION:

PERMITTING AGENT

Kaylene R. Gardner
EOG Resources, Inc.
P.O. Box 1815
Vernal, Ut 84078
(435) 781-9111


DRILLING OPERATIONS

Donald Presenkowski
EOG Resources, Inc.
P.O. Box 250
Big Piney, WY 83113
307-276-4865

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route; that I am familiar with the conditions which currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by EOG Resources, Inc. and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

Please be advised that EOG Resources, Inc. is considered to be the operator of the East Chapita 60-16 Well, located in the NENE, of Section 16, T9S, R23E, Uintah County, Utah; Federal land and minerals; and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond Coverage is under Bond # NM 2308.

March 16, 2007
Date


Kaylene R. Gardner, Sr. Regulatory Assistant

EOG RESOURCES, INC.
EAST CHAPITA #60-16
SECTION 16, T9S, R23E, S.L.B.&M.

PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 14.0 MILES TO THE JUNCTION OF STATE HIGHWAY 88; EXIT LEFT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 17.0 MILES TO OURAY, UTAH; PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 0.3 MILES ON THE SEEP RIDGE ROAD TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 12.3 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTH; TURN RIGHT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 1.7 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 1.9 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN RIGHT AND PROCEED IN A SOUTHEASTERLY DIRECTION APPROXIMATELY 0.5 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY, THEN SOUTHEASTERLY, THEN NORTHEASTERLY DIRECTION APPROXIMATELY 6.3 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHWEST; TURN LEFT AND PROCEED IN A NORTHWESTERLY DIRECTION APPROXIMATELY 0.6 MILES TO THE BEGINNING OF THE PROPOSED ACCESS FOR THE #48-16 TO THE NORTHWEST; FOLLOW ROAD FLAGS IN A NORTHWESTERLY, THEN EASTERLY DIRECTION APPROXIMATELY 0.35 MILES TO THE BEGINNING OF THE PROPOSED ACCESS TO THE NORTHEAST; FOLLOW ROAD FLAGS IN A NORTHEASTERLY DIRECTION APPROXIMATELY 0.35 MILES TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 55.3 MILES.

LOCATION LAYOUT FOR
EAST CHAPITA #60-16
SECTION 16, T9S, R23E, S.L.B.&M.
655' FNL 625' FEL

C-5.2'
El. 67.8'

SCALE: 1" = 50'
DATE: 08-30-06
Drawn By: S.L.

Flare Pit is to be located
a min. of 100' from the
Well Head.

A circular seal for a Registered Land Surveyor in the State of Utah. The outer ring contains the text "REGISTERED LAND SURVEYOR" at the top and "STATE OF UTAH" at the bottom. Inside the ring, the number "No. 161319" is printed. The name "ROBERT L. TAYLOR" is written across the center in a bold, slanted font. A signature, which appears to be "Robert L. Taylor", is written over the name and number.

F-3.2'
El. 59.4'

F-4.2'
El. 58.4'

El. 62.1' ~~_____~~ F-1.1
C-11.5' Reserve Pit Backfill El. 61.5'
(btm. pit) & Spoils Stockpile)

Elev. Ungraded Ground At Loc. Stake = 4965.1'

FINISHED GRADE ELEV. AT LOC. STAKE = 4962.6'

FIGURE #1


UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

EOG RESOURCES, INC.


TYPICAL CROSS SECTIONS FOR

EAST CHAPITA #60-16
SECTION 16, T9S, R23E, S.L.B.&M.
655' FNL 625' FEL

FIGURE #2



DATE: 08-30-06
Drawn By: S.L.



NOTE:

Topsoil should not be Stripped Below Finished Grade on Substructure Area.

* NOTE:

FILL QUANTITY INCLUDES 5% FOR COMPACTION

APPROXIMATE YARDAGES

CUT	
(6") Topsoil Stripping	= 1,580 Cu. Yds.
Remaining Location	= 6,090 Cu. Yds.
TOTAL CUT	= 7,670 CU.YDS.
FILL	= 4,430 CU.YDS.

EXCESS MATERIAL	= 3,240 Cu. Yds.
Topsoil & Pit Backfill (1/2 Pit Vol.)	= 3,240 Cu. Yds.
EXCESS UNBALANCE (After Interim Rehabilitation)	= 0 Cu. Yds.

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East • Vernal, Utah 84078 • (435) 789-1017

EOG RESOURCES, INC.

EAST CHAPITA #60-16

LOCATED IN UTAH COUNTY, UTAH
SECTION 16, T9S, R23E, S.L.B.&M.




PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: SOUTHERLY



PHOTO: VIEW FROM BEGINNING OF PROPOSED ACCESS

CAMERA ANGLE: NORTHEASTERLY



UELS

Uintah Engineering & Land Surveying

85 South 200 East Vernal, Utah 84078
435-789-1017 uels@uelsinc.com

- Since 1964 -

LOCATION PHOTOS


08 31 06
MONTH DAY YEAR

PHOTO

TAKEN BY: G.S.

DRAWN BY: C.P.

REVISED: 00-00-00



LEGEND:

- | | |
|-------------------|-------------------------|
| ○ DISPOSAL WELLS | ○ WATER WELLS |
| ● PRODUCING WELLS | ● ABANDONED WELLS |
| ● SHUT IN WELLS | ● TEMPORARILY ABANDONED |



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813



EOG RESOURCES, INC.


EAST CHAPITA #60-16
SECTION 16, T9S, R23E, S.L.B.&M.
655' FNL 625' FEL

TOPOGRAPHIC
MAP

08 31 06
 MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: C.P. REVISED: 00-00-00





APPROXIMATE TOTAL PIPELINE DISTANCE = 2,418' +/-

LEGEND:

- PROPOSED ACCESS ROAD
- - - PROPOSED PIPELINE
- - - PROPOSED PIPELINE (SERVICING OTHER WELLS)

N

EOG RESOURCES, INC.

EAST CHAPITA #60-16
SECTION 16, T9S, R23E, S.L.B.&M.
655' FNL 625' FEL



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC
MAP

08 31 06
 MONTH DAY YEAR

SCALE: 1" = 1000' DRAWN BY: C.P. REVISED: 00-00-00

D
TOPO

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 03/19/2007

API NO. ASSIGNED: 43-047-39150

WELL NAME: E CHAPITA 60-16

OPERATOR: EOG RESOURCES INC (N9550)

PHONE NUMBER: 435-781-9111

CONTACT: KAYLENE GARDNER

PROPOSED LOCATION:

NENE 16 090S 230E

SURFACE: 0655 FNL 0625 FEL

BOTTOM: 0655 FNL 0625 FEL

COUNTY: Uintah

LATITUDE: 40.04144 LONGITUDE: -109.3240

UTM SURF EASTINGS: 642982 NORTHINGS: 4433493

FIELD NAME: NATURAL BUTTES (630)

INSPECT LOCATN BY: / /

Tech Review

Initials

Date

Engineering

DKD

4/19/07

Geology

Surface

LEASE TYPE: 3 - State

LEASE NUMBER: ML-47045

SURFACE OWNER: 3 - State

PROPOSED FORMATION: WSMVD

COALBED METHANE WELL? NO

RECEIVED AND/OR REVIEWED:

☒ Plat

☒ Bond: Fed[] Ind[] Sta[] Fee[]
(No. 6196017)

☒ Potash (Y/N)

☒ Oil Shale 190-5 (B) or 190-3 or 190-13

☒ Water Permit

(No. 49-1501)

☒ RDCC Review (Y/N)

(Date:)

☒ Fee Surf Agreement (Y/N)

☒ Intent to Commingle (Y/N)

(Wasatch, mesa Verde)

LOCATION AND SITING:

___ R649-2-3.

Unit: _____

☒ R649-3-2. General

Siting: 460 From Qtr/Qtr & 920' Between Wells

___ R649-3-3. Exception

___ Drilling Unit

Board Cause No: _____

Eff Date: _____

Siting: _____

___ R649-3-11. Directional Drill

COMMENTS: _____

Print (3-6-07)

STIPULATIONS: _____

1- Spacing Shp

2- Commingle

3- STATEMENT OF BASIS

T9S R23E

NATURAL BUTTES FIELD

E CHAPITA
18-17E CHAPITA
57-16E CHAPITA
58-16E CHAPITA
60-16E CHAPITA
30-16

CWU 1

E CHAPITA
47-16E CHAPITA
48-16

CWU 29

16

E CHAPITA
31-16E CHAPITA
800-16E CHAPITA
49-16
COG STATE
33-16E CHAPITA
7-16

E CHAPITA 15-17

E CHAPITA
50-16E CHAPITA
8-16E CHAPITA
818-16E CHAPITA
6-16

CHAPITA WELLS UNIT

OPERATOR: EOG RESOURCES INC (N9550)

SEC: 16 T.9S R. 23E

FIELD: NATURAL BUTTES (630)

COUNTY: UINTAH

SPACING: R649-3-2 / GENERAL SITING

Field Status


- ABANDONED
- ACTIVE
- COMBINED
- INACTIVE
- PROPOSED
- STORAGE
- TERMINATED

Unit Status

- EXPLORATORY
- GAS STORAGE
- NF PP OIL
- NF SECONDARY
- PENDING
- PI OIL
- PP GAS
- PP GEOTHERML
- PP OIL
- SECONDARY
- TERMINATED

Wells Status

- GAS INJECTION
- GAS STORAGE
- LOCATION ABANDONED
- NEW LOCATION
- PLUGGED & ABANDONED
- PRODUCING GAS
- PRODUCING OIL
- SHUT-IN GAS
- SHUT-IN OIL
- TEMP. ABANDONED
- TEST WELL
- WATER INJECTION
- WATER SUPPLY
- WATER DISPOSAL
- DRILLING



Utah Oil Gas and Mining



PREPARED BY: DIANA MASON
DATE: 27-MARCH-2007

Application for Permit to Drill
Statement of Basis
Utah Division of Oil, Gas and Mining

3/26/2007

Page 1

APD No	API WellNo	Status	Well Type	Surf Ownr	CBM
293	43-047-39150-00-00		GW	S	No
Operator	EOG RESOURCES INC		Surface Owner-APD		
Well Name	E CHAPITA 60-16		Unit		
Field	UNDESIGNATED		Type of Work		
Location	NENE 16 9S 23E S 655 FNL 625 FEL GPS Coord (UTM) 642982E 4433493N				

Geologic Statement of Basis

EOG proposes to set 45 feet of conductor and 2,300 feet of surface casing cemented to the surface. The base of the moderately saline water is estimated at approximately 1,000 feet. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the proposed location. The surface formation at this location is the Uinta Formation. The Uinta Formation is made up of discontinuous sands interbedded with shales and are not expected to produce prolific aquifers. The proposed surface casing should adequately protect any near surface aquifers.

Brad Hill
APD Evaluator

3/26/2007
Date / Time

Surface Statement of Basis

The general area is within the Coyote Wash Drainage. This drainage is a major drainage beginning near the Utah-Colorado border to the east and joining the White River approximately 6 miles to the southwest. The drainage consists of several significant side drainages. The drainage is dry except for ephemeral flows. No seeps or springs exist in the area. An occasional pond has been constructed to supply water for livestock and antelope. The topography is characterized by rolling hills, frequently divided by gentle to deep draws, which flow into Coyote Wash. The draws are often rimmed with steep side hills with exposed sand stone bedrock cliffs. Vernal, Utah is approximately 35 air miles and 55 road miles to the northwest. The area is accessed by Utah State, Uintah County and oilfield development Roads to with 0.35 miles of the location where a new road will be constructed.

The proposed East Chapita 60-16 gas well is on a narrow broken ridge top between two forks of Coyote Wash. The main wash is about ¼ mile to the northeast. The ridge breaks off moderately steep on the southwest and northeast sides. No drainage concerns exist.

Both the surface and minerals for this location are owned by SITLA. Jim Davis of SITLA attended the pre-site visit and had no concerns regarding the proposed location.

Ben Williams represented the Utah Division of Wildlife Resources. Mr. Williams stated the area is classified as critical yearlong habitat for antelope. He however recommended no stipulations for this species as the loss of forage from this location is not significant and water not forage is the factor limiting the herd population in the area. No other wildlife is expected to be affected. He gave Byron Tolman, representing EOG Resources, and Mr. Davis a copy of his evaluation and a DWR recommended seed mix to use when re-vegetating the area.

The location appears to be the best site for constructing and operating a well in the immediate area.

Floyd Bartlett
Onsite Evaluator

3/6/2007
Date / Time

Application for Permit to Drill
Statement of Basis
Utah Division of Oil, Gas and Mining

3/26/2007

Page 2

Conditions of Approval / Application for Permit to Drill

Category Condition

Pits

Pits A synthetic liner with a minimum thickness of 16 mils with a felt subliner shall be properly installed and maintained in the reserve pit.

ON-SITE PREDRILL EVALUATION

Utah Division of Oil, Gas and Mining

Operator EOG RESOURCES INC
Well Name E CHAPITA 60-16
API Number 43-047-39150-0 **APD No** 293 **Field/Unit** UNDESIGNATED
Location: 1/4,1/4 NENE **Sec** 16 **Tw** 9S **Rng** 23E 655 FNL 625 FEL
GPS Coord (UTM) 642978 4433496 **Surface Owner**

Participants

Floyd Bartlett (DOGM), Jim Davis (SITLA), Byron Tolman (Agent for EOG Resources) and Ben Williams (UDWR).

Regional/Local Setting & Topography

The general area is within the Coyote Wash Drainage. This drainage is a major drainage beginning near the Utah-Colorado border to the east and joining the White River approximately 6 miles to the southwest. The drainage consists of several significant side drainages. The drainage is dry except for ephemeral flows. No seeps or springs exist in the area. An occasional pond has been constructed to supply water for livestock and antelope. The topography is characterized by rolling hills, frequently divided by gentle to deep draws, which flow into Coyote Wash. The draws are often rimmed with steep side hills with exposed sand stone bedrock cliffs. Vernal, Utah is approximately 35 air miles and 55 road miles to the northwest. The area is accessed by Utah State, Uintah County and oilfield development Roads to within 0.35 miles of the location where a new road will be constructed.

The proposed East Chapita 60-16 gas well is on a narrow broken ridge top between two forks of Coyote Wash. The main wash is about ¼ mile to the northeast. The ridge breaks off moderately steep on the southwest and northeast sides. No drainage concerns exist.

Both the surface and minerals for this location are owned by SITLA. Jim Davis of SITLA attended the pre-site visit and had no concerns regarding the proposed location.

Surface Use Plan

Current Surface Use

Grazing
Recreational
Wildlife Habitat

New Road

Miles	Well Pad		Src Const Material	Surface Formation
0.35	Width 261	Length 325	Onsite	UNTA

Ancillary Facilities N

Waste Management Plan Adequate? Y

Environmental Parameters

Affected Floodplains and/or Wetland N

Flora / Fauna

Open big sagebrush type. Halogeton, shadscale, cheatgrass and curly mesquite are present.

Antelope, coyote, small mammals and birds. Winter domestic sheep grazing

Soil Type and Characteristics

Rocky sandy loam with some bedrock in location.

Erosion Issues N**Sedimentation Issues** N**Site Stability Issues** N**Drainage Diversion Required** Y**Berm Required?** N**Erosion Sedimentation Control Required?** N**Paleo Survey Run?****Paleo Potential Observed?** Y**Cultural Survey Run?** Y**Cultural Resources?** N**Reserve Pit****Site-Specific Factors****Site Ranking**

Distance to Groundwater (feet)	>200	0
Distance to Surface Water (feet)	>1000	0
Dist. Nearest Municipal Well (ft)	>5280	0
Distance to Other Wells (feet)	300 to 1320	10
Native Soil Type	Mod permeability	10
Fluid Type	Fresh Water	5
Drill Cuttings	Normal Rock	0
Annual Precipitation (inches)	<10	0
Affected Populations	<10	0
Presence Nearby Utility Conduits	Not Present	0

Final Score 25 1 **Sensitivity Level****Characteristics / Requirements**

The reserve pit is proposed on the southwest portion of the location within an area of cut. Dimensions are 75' x 147' x 12' deep. A liner is required. EOG customarily uses a 16 mil liner with an appropriate thickness of sub-felt to cushion the liner.

Closed Loop Mud Required? N**Liner Required?** Y**Liner Thickness** 16**Pit Underlayment Required?** Y**Other Observations / Comments**

ATV's were used to access the site.

Floyd Bartlett

Evaluator

3/6/2007

Date / Time

2007-04 EOG E Chapita 00-16

Casing Schematic

BHP $0.052(9070) 10.5 = 4952 \text{ psi}$
anticipate 4952

Gravel $12(9070) = 1088$
 $4952 - 1088 = 3864 \text{ psi, MASS}$

BOPE SM

Burst 3520
70% 2464 psi

Max P @ surf. shoe

$.22(6770) = 1489$

$4952 - 1489 = 3463 \text{ psi}$

Test to 2464 psi

Stop prod cmt?

9-5/8"
MW 8.4
Frac 19.3

4-1/2"
MW 10.5

Surface

12 1/2%

18 3/4%

Uinta

* surface stop

TOC @ 801

1000' ± BMSW

1716' Green River

Surface
2300. MD

TOC @ 3840.

4649' Wasatch

5224' Chapita Wells

5915' Buck Canyon

6478' North Horn

6826' KMV Price River

7621' KMV Price River Middle

8479' KMV Price River Lower

8867' Sego

Production
9070. MD

Well name:	2007-04 EOG E Chapita 60-16	
Operator:	EOG Resources Inc.	
String type:	Surface	Project ID: 43-047-39150
Location:	Uintah County	

Design parameters:
Collapse

Mud weight: 8.400 ppg
Design is based on evacuated pipe.

Minimum design factors:
Collapse:

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 107 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 290 ft

Cement top: 801 ft

Burst

Max anticipated surface pressure: 2,024 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 2,300 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on buoyed weight.

Neutral point: 2,014 ft

Non-directional string.
Re subsequent strings:

Next setting depth: 9,070 ft
Next mud weight: 10.500 ppg
Next setting BHP: 4,947 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 2,300 ft
Injection pressure: 2,300 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	2300	9.625	36.00	J-55	ST&C	2300	2300	8.796	998.2

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	1004	2020	2.013	2300	3520	1.53	72	394	5.43 J

Prepared Helen Sadik-Macdonald
by: Div of Oil, Gas & Minerals

Phone: 801-538-5357
FAX: 801-359-3940

Date: April 11, 2007
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 2300 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

Well name:	2007-04 EOG E Chapita 60-16	
Operator:	EOG Resources Inc.	
String type:	Production	Project ID: 43-047-39150
Location:	Uintah County	

Design parameters:
Collapse

Mud weight: 10.500 ppg
Design is based on evacuated pipe.

Minimum design factors:
Collapse:

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 202 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,500 ft

Cement top: 3,840 ft

Burst

Max anticipated surface pressure: 2,952 psi
Internal gradient: 0.220 psi/ft
Calculated BHP 4,947 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Non-directional string.

Tension is based on buoyed weight.
Neutral point: 7,646 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	9070	4.5	11.60	N-80	LT&C	9070	9070	3.875	791.5

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	4947	6350	1.284	4947	7780	1.57	89	223	2.51 J

Prepared Helen Sadik-Macdonald
by: Div of Oil, Gas & Minerals

Phone: 801-538-5357
FAX: 801-359-3940

Date: April 11, 2007
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 9070 ft, a mud weight of 10.5 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

From: <Kaylene_Gardner@eogresources.com>
To: "Dustin Doucet" <dustindoucet@utah.gov>
Date: 4/18/2007 5:54 PM
Subject: Re: Commingling APD..more
Attachments: ECW 60-16.doc; ECW 58-16.doc; ECW 57-16.doc

The commingling information is within the Drilling plan - I attached a copy for your reference.

Kaylene Gardner
EOG/Vernal
435-781-9111 Office

"Dustin Doucet" <dustindoucet@utah.gov>
04/18/2007 04:46 PM

To
<Kaylene_Gardner@eogresources.com>
cc

Subject
Commingling APD..more

Kaylene,

I need the same info mentioned below on a couple more APD's... the E Chapita 57-16 and 58-16. Thanks.

Dustin

Dustin K. Doucet
Petroleum Engineer
Utah Division of Oil, Gas and Mining
Oil and Gas Program
1594 West North Temple, Suite 1210
Salt Lake City, UT 84116

Phone: (801) 538-5281
fax: (801) 359-3940
email: dustindoucet@utah.gov

>>> Dustin Doucet 4/18/2007 3:35 PM >>>
Kaylene,

I was just reviewing the E Chapita 60-16 well and had everything except the commingling request (i.e. had the plat and affidavit, but nothing requesting commingling and how you propose to do that). If you could send that portion to me I will include it in the APD and sign off on it.
thanks.

Dustin

Dustin K. Doucet
Petroleum Engineer
Utah Division of Oil, Gas and Mining
Oil and Gas Program
1594 West North Temple, Suite 1210
Salt Lake City, UT 84116

Phone: (801) 538-5281
fax: (801) 359-3940
email: dustindoucet@utah.gov

EIGHT POINT PLAN**east chapita 60-16****NE/NE, SEC. 16, T9S, R23E, S.L.B.&M..****UINTAH COUNTY, UTAH****1. & 2. ESTIMATED TOPS & ANTICIPATED OIL, GAS, & WATER ZONES:**

FORMATION	TVD-RKB (ft)	Objective	Lithology	
Green River	1,716		Shale	
Wasatch	4,649	Primary	Sandstone	Gas
Chapita Wells	5,224	Primary	Sandstone	Gas
Buck Canyon	5,915	Primary	Sandstone	Gas
North Horn	6,478	Primary	Sandstone	Gas
KMV Price River	6,826	Primary	Sandstone	Gas
KMV Price River Middle	7,621	Primary	Sandstone	Gas
KMV Price River Lower	8,479	Primary	Sandstone	Gas
Sego	8,867		Sandstone	
TD	9,070			

Estimated TD: 9,070' or 200'± below Sego top

Anticipated BHP: 4,952 Psig

1. Fresh Waters may exist in the upper, approximately 1,000 ft ± of the Green River Formation, with top at about 2,000 ft ±.
2. Cement isolation is installed to surface of the well isolating all zones by cement.

EOG Resources, Inc. requests authorization for commingling of production from the Wasatch, and Mesaverde formations in the referenced wellbore. In the event allocation of production is necessary, the allocation will be based on proportionate net pay as calculated from cased hole logs. Production from the Wasatch, and Mesaverde formations will be commingled in the wellbore and produced through open ended 2-3/8" tubing landed below all perforations in the 4-1/2" production casing.

Attached is a map showing the location of all wells on contiguous oil and gas leases or drilling units and an affidavit showing that this application has been provided to owners of all contiguous oil and gas leases or drilling units overlying the pool.

3. PRESSURE CONTROL EQUIPMENT:

Production Hole – 5000 Psig
BOP schematic diagrams attached.

EIGHT POINT PLAN

east chapita 60-16
NE/NE, SEC. 16, T9S, R23E, S.L.B.&M..
UINTAH COUNTY, UTAH

4. CASING PROGRAM:

<u>CASING</u>	<u>Hole Size</u>	<u>Length</u>	<u>Size</u>	<u>WEIGHT</u>	<u>Grade</u>	<u>Thread</u>	<u>Rating Collapse</u>	<u>Factor Burst</u>	<u>Tensile</u>
Conductor	17 1/2"	0 – 45'	13 3/8"	48.0#	H-40	STC	770 PSI	1730 PSI	322,000#
Surface	12 1/4"	0 – 2,300' KB±	9-5/8"	36.0#	J-55	STC	2020 PSI	3520 Psi	394,000#
Production	7-7/8"	Surface – TD	4-1/2"	11.6#	N-80	LTC	6350 PSI	7780 Psi	223,000#

Note: 12-1/4" surface hole will be drilled to a total depth of 200'± below the base of the Green River lost circulation zone and cased w/9-5/8" as shown to that depth. Drilled depth may be shallower or deeper than the 2300' shown above depending on the actual depth of the loss zone.

All casing will be new or inspected.

5. Float Equipment:**Surface Hole Procedure (0' - 2300'±)**

Guide Shoe

Insert Float Collar (PDC drillable)

Centralizers: 1-5' above shoe, top of jts. #2 and #3 then every 5th joint to surface. (15 total)

Production Hole Procedure (2300'± - TD):

Float shoe, 1 joint casing, float collar and balance of casing to surface. 4-1/2", 11.6#, N-80 or equivalent marker collars or short casing joints to be placed at top of Price River and 400' above top of Wasatch. Centralizers to be placed 5' above shoe on joint #1, top of joint #2, and every 2nd joint to 400' above Wasatch Island top. Thread lock float shoe, top and bottom of float collar, and top of 2nd joint.

6. MUD PROGRAM**Surface Hole Procedure (Surface - 2300'±):**

Air/air mist or aerated water.

Production Hole Procedure (2300'± - TD): Anticipated mud weight 9.5 – 10.5 ppg depending on actual wellbore conditions encountered while drilling.

EIGHT POINT PLAN**east chapita 60-16****NE/NE, SEC. 16, T9S, R23E, S.L.B.&M..****UINTAH COUNTY, UTAH**

2300'± - TD A closed mud system will be utilized. A bentonite gelled water mud system will be used to control viscosity w/PHPA polymer used for supplemental viscosity and clay encapsulation/inhibition. Water loss will be maintained at <15cc's using white starch or PAC. Bactericides will be used as needed. Anticipated pH will range from 9.0-10.0. Mud weight will be adjusted as necessary for well control. Deflocculants/thinners will be used as necessary to maintain mud quality. LCM sweeps will be utilized as necessary to control lost circulation and mud loss. CO2 contamination, if encountered, will be treated with lime and gypsum.

7. VARIANCE REQUESTS:

Reference: Onshore Oil and Gas Order No. 2 – Item E: Special Drilling Operations

EOG Resources, Inc. requests a variance to regulations requiring the blooie line to be 100' in length. Due to reduce location excavation, the blooie line will be approximately 75' in length

8. EVALUATION PROGRAM:

Logs: Mud log from base of surface casing to TD.
Cased-hole Logs: Cased-hole logs will be run in lieu of open-hole logs consisting of the following:
Cement Bond / Casing Collar Locator and Pulsed Neutron

9. CEMENT PROGRAM:**Surface Hole Procedure (Surface - 2300'±):**

Lead: 185 sks Class "G" cement with 16% Gel, 10 #/sx Gilsonite, 3% Salt, 2% CaCl₂, 3 lb/sx GR3 ¼ #/sx Flocele mixed at 11 ppg, 3.82 ft³/sk. yield, 23 gps water.

Tail: 207 sks Class "G" cement with 2% CaCl₂, ¼#/sk Flocele mixed at 15.6 ppg, 1.18 ft³/sk., 5.2 gps water.

Top Out: As necessary with Class "G" cement with 2% CaCl₂, ¼#/sk Flocele mixed at 15.6 ppg, 1.18 ft³/sk., 5.2 gps water.

Note: Cement volumes will be calculated to bring lead cement to surface and tail cement to 500' above the casing shoe.

EIGHT POINT PLAN

east chapita 60-16
NE/NE, SEC. 16, T9S, R23E, S.L.B.&M..
UINTAH COUNTY, UTAH

Production Hole Procedure (2300'± - TD)

Lead: 135 sks: Hi-Lift "G" w/12% D20 (Bentonite), 1% D79 (Extender), 5% D44 (Salt), 0.2% D46 (Antifoam), 0.25% D112 (Fluid Loss Additive), 0.25 pps D29 (cello flakes) mixed at 11.0 ppg, 3.91 ft³/sk., 24.5 gps water.

Tail: 870 sks: 50:50 Poz "G" w/ 2% D20 (Bentonite), 0.1% D46 (Antifoam), 0.075% D13 (Retarder), 0.2% D167 (Fluid Loss Additive), 0.2% D65 (Dispersant), mixed at 14.1 ppg, 1.28 ft³/sk., 5.9gps water.

Note: The above number of sacks is based on gauge-hole calculation.
Lead volume to be calculated to bring cement to 200'± above 9-5/8" casing shoe.
Tail volume to be calculated to bring cement to 400'± above top of Wasatch.

Final Cement volumes will be based upon gauge-hole plus 45% excess.

10. ABNORMAL CONDITIONS:**Surface Hole (Surface - 2300'±):**

Lost circulation

Production Hole (2300'± - TD):

Sloughing shales, lost circulation and key seat development are possible in the Wasatch Formation.

11. STANDARD REQUIRED EQUIPMENT:

- A. Choke Manifold
- B. Upper and Lower Kelly Cock
- C. Stabbing Valve
- D. Visual Mud Monitoring

12. HAZARDOUS CHEMICALS:

No chemicals subject to reporting under SARA title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.

(Attachment: BOP Schematic Diagram)

From: Ed Bonner
To: Mason, Diana
Date: 4/23/2007 3:38 PM
Subject: Well Clearance

CC: Davis, Jim; Garrison, LaVonne; Hill, Brad; Hunt, Gil

The following wells have been given cultural resources clearance by the Trust Lands Cultural Resources Group:

Bill Barrett Corporation

Peters Point State 8-2D-13-16 (API 43 007 31280)

EnCana Oil & Gas (USA) Inc

Middle Mountain State 36-12-29-24 (API 43 037 31855)

EOG Resources, Inc

East Chapita 60-16 (API 43 047 39150)

East Chapita 57-16 (API 43 047 39151)

East Chapita 58-16 (API 43 047 39152)

Kerr McGee Oil & Gas Onshore LP

NBU 1021-13N (API 43 047 39107)

NBU 1021-13H (API 43 047 39108)

NBU 1021-16D (API 43 047 39109)

NBU 1022-19P (API 43 047 39139)

If you have any questions regarding this matter please give me a call.



State of Utah

Department of Natural Resources

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas & Mining

JOHN R. BAZA
Division Director

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

April 24, 2007

EOG Resources, Inc
1060 East Highway 40
Vernal, UT 84078

Re: East Chapita 60-16 Well, 655' FNL, 625' FEL, NE NE, Sec. 16, T. 9 South,
R. 23 East, Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

Administrative approval for commingling the production from the Wasatch formation and the Mesaverde formation in this well is hereby granted. Appropriate information has been submitted to DOGM in accordance with R649-3-22. No written objections from owners were received by DOGM.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-39150.

Sincerely,

Gil Hunt
Associate Director

pab
Enclosures

cc: Uintah County Assessor
SITLA

Operator: EOG Resources, Inc
Well Name & Number East Chapita 60-16
API Number: 43-047-39150
Lease: ML-47045

Location: NE NE Sec. 16 T. 9 South R. 23 East

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

The operator is required to notify the Division of Oil, Gas and Mining of the following action during drilling of this well:

- 24 hours prior to cementing or testing casing – contact Dan Jarvis
- 24 hours prior to testing blowout prevention equipment – contact Dan Jarvis
- 24 hours prior to spudding the well – contact Carol Daniels
- Within 24 hours of any emergency changes made to the approved drilling program – contact Dustin Doucet
- Prior to commencing operations to plug and abandon the well – contact Dan Jarvis

The operator is required to get approval from the Division of Oil, Gas and Mining before performing any of the following actions during the drilling of this well:

- Plugging and abandonment or significant plug back of this well – contact Dustin Doucet
- Any changes to the approved drilling plan – contact Dustin Doucet

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voice mail message if the person is not available to take the call):

- Dan Jarvis at: (801) 538-5338 office
(801) 942-0873 home
- Carol Daniels at: (801) 538-5284 office
- Dustin Doucet at: (801) 538-5281 office
(801) 733-0983 home

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. Compliance with the State of Utah Antiquities Act forbids disturbance of archeological, historical, or paleontological remains. Should archeological, historical or paleontological remains be encountered during your operations, you are required to immediately suspend all operations and immediately inform the Trust Lands Administration and the Division of State History of the discovery of such remains.
5. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)
6. This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: EOG Resources, Inc. Operator Account Number: N 9550
Address: 600 17th St., Suite 1000N
city Denver
state CO zip 80202 Phone Number: (303) 824-5526

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
43-047-39150	East Chapita 60-16		NENE	16	9S	23E	Uintah
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
A	99999	16784	4/5/2008			4/24/08	
Comments: <u>Wasatch/Mesaverde well</u>							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

Mary A. Maestas

Name (Please Print)

Mary A. Maestas

Signature

Regulatory Assistant

Title

4/7/2008

Date

RECEIVED

APR 07 2008

DIV. OF OIL, GAS & MINING

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of Company: EOG RESOURCES INC

Well Name: E CHAPITA 60-16

Api No: 43-047-39150 Lease Type: STATE

Section 16 Township 09S Range 23E County UINTAH

Drilling Contractor CRAIG'S ROUSTABOUT SERV RIG # RATHOLE

SPUDDED:

Date 04/05/08

Time 11:30 AM

How DRY

Drilling will Commence: _____

Reported by JERRY BARNES

Telephone # (435) 828-1720

Date 04/07/08 Signed CHD

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.


1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-47045
2. NAME OF OPERATOR: EOG Resources, Inc.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 600 17th St., Suite 1000N CITY Denver STATE CO ZIP 80202		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: 655' FNL & 625' FEL 40.041408 LAT 109.324756 LON QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENE 16 9S 23E S		8. WELL NAME and NUMBER: East Chapita 60-16 9. API NUMBER: 43-047-39150 10. FIELD AND POOL, OR WILDCAT: Natural Buttes/Wasatch/Mesaverde
		PHONE NUMBER: (303) 824-5526
		COUNTY: Uintah STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: Well spud
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The referenced well spud on 4/5/2008.

NAME (PLEASE PRINT) Mary A. Maestas	TITLE Regulatory Assistant
SIGNATURE 	DATE 4/7/2008

(This space for State use only)

RECEIVED

APR 10 2008

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☒ OTHER _____

2. NAME OF OPERATOR:
EOG Resources, Inc.

3. ADDRESS OF OPERATOR:
600 17th St., Suite 1000N CITY Denver STATE CO ZIP 80202

PHONE NUMBER:
(303) 824-5526

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 655' FNL & 625' FEL 40.041408 LAT 109.324756 LON

COUNTY: Uintah

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENE 16 9S 23E S

STATE: UTAH

5. LEASE DESIGNATION AND SERIAL NUMBER:
ML-47045

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

8. WELL NAME and NUMBER:
East Chapita 60-16

9. API NUMBER:
43-047-39150

10. FIELD AND POOL, OR WILDCAT:
Natural Buttes/Wasatch/Mesaverde

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input checked="" type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The referenced well was turned to sales on 6/12/2008. Please see the attached operations summary report for drilling and completion operations performed on the subject well.

NAME (PLEASE PRINT) Mary A. Maestas

TITLE Regulatory Assistant

SIGNATURE

Mary A. Maestas

DATE 6/16/2008

(This space for State use only)

RECEIVED

JUN 17 2008

WELL CHRONOLOGY REPORT

Report Generated On: 06-16-2008

Well Name	ECW 060-16	Well Type	DEVG	Division	DENVER
Field	CHAPITA DEEP	API #	43-047-39150	Well Class	COMP
County, State	UINTAH, UT	Spud Date	04-30-2008	Class Date	
Tax Credit	N	TVD / MD	9,070/ 9,070	Property #	059620
Water Depth	0	Last CSG	2.375	Shoe TVD / MD	0/ 0
KB / GL Elev	4,979/ 4,963				
Location	Section 16, T9S, R23E, NENE, 655 FNL & 625 FEL				

Event No	1.0	Description	DRILL & COMPLETE		
Operator	EOG RESOURCES, INC	WI %	100.0	NRI %	81.0

AFE No	304178	AFE Total	2,019,400	DHC / CWC	880,700/ 1,138,700
Rig Contr	TRUE	Rig Name	TRUE #31	Start Date	06-07-2007
06-07-2007	Reported By	SHARON CAUDILL			
Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$0	Completion	\$0	Well Total	\$0
MD	0	TVD	0	Progress	0
Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0	

Activity at Report Time: LOCATION DATA

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION DATA
			655' FNL & 625' FEL (NE/NE)
			SECTION 16, T9S, R23E
			UINTAH COUNTY, UTAH
			LAT 40.041408, LONG 109.324756 (NAD 27)
			LAT 40.041433, LONG 109.324078 (NAD 83)
			TRUE #31
			OBJECTIVE: 9070' TD, MESAVERDE
			DW/GAS
			EAST CHAPITA PROSPECT
			DD&A: CHAPITA DEEP
			NATURAL BUTTES FIELD
			LEASE: ML-47045
			ELEVATION: 4965.1' NAT GL, 4962.6' PREP GL (DUE TO ROUNDING THE PREP GL IS 4963'), 4979' KB (16')
			EOG WI 100%, NRI 81%

03-17-2008 Reported By TERRY CSERE

Daily Costs: Drilling	\$38,000	Completion	\$0	Daily Total	\$38,000
Cum Costs: Drilling	\$38,000	Completion	\$0	Well Total	\$38,000
MD	0	TVD	0	Progress	0
Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0	

Activity at Report Time: LOCATION BUILD

Start	End	Hrs	Activity Description
06:00	06:00	24.0	START CONSTRUCTION OF LOCATION.

03-18-2008 Reported By TERRY CSERE

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$38,000	Completion	\$0	Well Total	\$38,000
MD	0	TVD	0	Progress	0
Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0	

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION IS 10% COMPLETE.

03-19-2008 Reported By TERRY CSERE

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$38,000	Completion	\$0	Well Total	\$38,000
MD	0	TVD	0	Progress	0
Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0	

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION IS 20% COMPLETE.

03-20-2008 Reported By TERRY CSERE

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$38,000	Completion	\$0	Well Total	\$38,000
MD	0	TVD	0	Progress	0
Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0	

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION 25% COMPLETE.

03-21-2008 Reported By TERRY CSERE

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$38,000	Completion	\$0	Well Total	\$38,000
MD	0	TVD	0	Progress	0
Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0	

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION 80% COMPLETE.

03-22-2008 Reported By TERRY CSERE

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$38,000	Completion	\$0	Well Total	\$38,000

MD	0	TVD	0	Progress	0	Days	0	MW	0.0	Visc	0.0
Formation :		PBTD : 0.0		Perf :		PKR Depth : 0.0					

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION 85% COMPLETE.

03-23-2008 Reported By TERRY CSERE

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$38,000	Completion	\$0	Well Total	\$38,000

MD	0	TVD	0	Progress	0	Days	0	MW	0.0	Visc	0.0
Formation :		PBTD : 0.0		Perf :		PKR Depth : 0.0					

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	PUSHING OUT PIT.

03-24-2008 Reported By TERRY CSERE

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$38,000	Completion	\$0	Well Total	\$38,000

MD	0	TVD	0	Progress	0	Days	0	MW	0.0	Visc	0.0
Formation :		PBTD : 0.0		Perf :		PKR Depth : 0.0					

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	ROCKED OUT.

03-25-2008 Reported By TERRY CSERE

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$38,000	Completion	\$0	Well Total	\$38,000

MD	0	TVD	0	Progress	0	Days	0	MW	0.0	Visc	0.0
Formation :		PBTD : 0.0		Perf :		PKR Depth : 0.0					

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION 85% COMPLETE.

03-26-2008 Reported By TERRY CSERE

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$38,000	Completion	\$0	Well Total	\$38,000

MD	0	TVD	0	Progress	0	Days	0	MW	0.0	Visc	0.0
Formation :		PBTD : 0.0		Perf :		PKR Depth : 0.0					

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	PUSHING OUT PIT.

03-27-2008 Reported By TERRY CSERE

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$38,000	Completion	\$0	Well Total	\$38,000
MD	0	TVD	0	Progress	0
Days	0	MW	0.0	Visc	0.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
-------	-----	-----	----------------------

06:00	06:00	24.0	ROCKED OUT.
-------	-------	------	-------------

03-28-2008 **Reported By** TERRY CSERE

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$38,000	Completion	\$0	Well Total	\$38,000
MD	0	TVD	0	Progress	0
Days	0	MW	0.0	Visc	0.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
-------	-----	-----	----------------------

06:00	06:00	24.0	DRILL ROCK AND SHOOT TODAY.
-------	-------	------	-----------------------------

03-31-2008 **Reported By** TERRY CSERE

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$38,000	Completion	\$0	Well Total	\$38,000
MD	0	TVD	0	Progress	0
Days	0	MW	0.0	Visc	0.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
-------	-----	-----	----------------------

06:00	06:00	24.0	LOCATION HAS BEEN SHOT. START PUSHING TOMORROW.
-------	-------	------	---

04-01-2008 **Reported By** TERRY CSERE

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$38,000	Completion	\$0	Well Total	\$38,000
MD	0	TVD	0	Progress	0
Days	0	MW	0.0	Visc	0.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
-------	-----	-----	----------------------

06:00	06:00	24.0	PUSHING ON LOCATION AND WILL SHOOT PORTION OF ROAD.
-------	-------	------	---

04-02-2008 **Reported By** TERRY CSERE

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$38,000	Completion	\$0	Well Total	\$38,000
MD	0	TVD	0	Progress	0
Days	0	MW	0.0	Visc	0.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
-------	-----	-----	----------------------

06:00	06:00	24.0	PUSHING OUT PIT.
-------	-------	------	------------------

04-03-2008 **Reported By** TERRY CSERE

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$38,000	Completion	\$0	Well Total	\$38,000
MD	0	TVD	0	Progress	0
Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0	

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LINE MONDAY.

04-04-2008 Reported By TERRY CSERE

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$38,000	Completion	\$0	Well Total	\$38,000
MD	0	TVD	0	Progress	0
Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0	

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LINE MONDAY.

04-05-2008 Reported By TERRY CSERE

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$38,000	Completion	\$0	Well Total	\$38,000
MD	0	TVD	0	Progress	0
Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0	

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LINE TOMORROW.

04-07-2008 Reported By JERRY BARNES

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$38,000	Completion	\$0	Well Total	\$38,000
MD	60	TVD	60	Progress	0
Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0	

Activity at Report Time: WO/AIR RIG

Start	End	Hrs	Activity Description
06:00	06:00	24.0	CRAIGS ROUSTABOUT SERVICE SPUD A 20" HOLE ON 04/05/08 @ 11:30 AM. SET 60' OF 14" CONDUCTOR. CEMENT TO SURFACE WITH READY MIX. JERRY BARNES NOTIFIED CAROL DANIELS W/UDOGM AND MICHAEL LEE W/BLM OF THE SPUD 04/05/08 @ 11:00 AM.

04-08-2008 Reported By JERRY BARNES

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$38,000	Completion	\$0	Well Total	\$38,000
MD	60	TVD	60	Progress	0
Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0	

Activity at Report Time: BUILD LOCATION/WO AIR RIG

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LINE TODAY.

04-09-2008 Reported By TERRY CSERE

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$38,000	Completion	\$0	Well Total	\$38,000

MD	60	TVD	60	Progress	0	Days	0	MW	0.0	Visc	0.0
----	----	-----	----	----------	---	------	---	----	-----	------	-----

Formation :	PBTD : 0.0	Perf :	PKR Depth : 0.0
-------------	------------	--------	-----------------

Activity at Report Time: WO AIR RIG

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION COMPLETE.

04-24-2008 Reported By JERRY BARNES

Daily Costs: Drilling	\$209,128	Completion	\$0	Daily Total	\$209,128
Cum Costs: Drilling	\$247,128	Completion	\$0	Well Total	\$247,128

MD	2,475	TVD	2,475	Progress	0	Days	0	MW	0.0	Visc	0.0
----	-------	-----	-------	----------	---	------	---	----	-----	------	-----

Formation :	PBTD : 0.0	Perf :	PKR Depth : 0.0
-------------	------------	--------	-----------------

Activity at Report Time: WORT

Start	End	Hrs	Activity Description
06:00	06:00	24.0	MIRU ASPEN DRILLING RIG # 14 ON 4/15/2008. DRILLED 12-1/4" HOLE TO 2506' GL. RAN 58 JTS (2459.28') OF 9-5/8", 36.0#, J-55, ST&C CASING WITH TOPCO GUIDE SHOE AND FLOAT COLLAR. 8 CENTRALIZERS SPACED MIDDLE OF SHOE JOINT AND EVERY COLLAR TILL GONE. LANDED @ 2475' KB. RAN 200' OF 1" PIPE DOWN BACKSIDE. RDMO AIR RIG.

MIRU HALLIBURTON CEMENTERS. PRESSURE TESTED LINES AND CEMENT VALVE TO 2500 PSIG. PUMPED 155 BBLs FRESH WATER & 20 BBLs GELLED WATER FLUSH AHEAD OF CEMENT. MIXED & PUMPED 200 SX (146 BBLs) OF PREMIUM LEAD CEMENT W/ 0.2% VARASET, 2% CALSEAL, & 2% EX-1. MIXED LEAD CEMENT @ 10.5 PPG W/ YIELD OF 4.10 CF/SX.

TAILED IN W/ 200 SX (42 BBLs) OF PREMIUM CEMENT W/ 2 % CACL2. MIXED TAIL CEMENT TO 15.6 W/ YIELD OF 1.18 CF/SX. DISPLACED CEMENT W/ 186.5 BBLs FRESH WATER. BUMPED PLUG W/ 850# @ 6:30 PM, 4/19/2008. CHECKED FLOAT, FLOAT HELD. SHUT-IN CASING VALVE. BROKE CIRCULATION 135 BBLs INTO FRESH WATER FLUSH. NO CEMENT TO SURFACE. HOLE FELL BACK WHEN PLUG BUMPED.

TOP JOB # 1: PUMP DOWN 200' OF 1" PIPE. MIXED & PUMPED 200 SX (41 BBLs) OF PREMIUM CEMENT W/ 2 % CACL2. MIXED CEMENT @ 15.8 PPG W/ YIELD OF 1.15 CF/SX. NO RETURNS. WOC 3 HRS.

TOP JOB # 2: MIXED & PUMPED 200 SX (41 BBLs) OF PREMIUM CEMENT W/ 2% CACL2. MIXED CEMENT @ 15.8 PPG W/ YIELD OF 1.15 CF/SX. HOLE FILLED & STOOD FULL. RDMO HALLIBURTON CEMENTERS.

PREPARED LOCATION FOR ROTARY RIG. WORT. WILL DROP FROM REPORT UNTIL FURTHER ACTIVITY.

ASPEN DRILLING TOOK SURVEYS WHILE DRILLING @ 517'-1.0°, 993'-0.75°, 1507'-0.80°, 2117'-1.0°.

CONDUCTOR LEVEL RECORD: PS= 89.9 OPS= 89.9 VDS= 90.0 MS= 90.0.

9 5/8 CASING LEVEL RECORD: PS= 90.0 OPS= 89.9 VDS= 89.7 MS= 89.7.

LESTER FARNSWORTH NOTIFIED ROOSEVELT OFFICE W/ UDOGM OF THE SURFACE CASING & CEMENT JOB ON 4/16/2008 @ 1:00 P.M.

04-30-2008 Reported By PAT CLARK

Daily Costs: Drilling	\$33,470	Completion	\$350	Daily Total	\$33,820
Cum Costs: Drilling	\$280,598	Completion	\$350	Well Total	\$280,948
MD	2,475	TVD	2,475	Progress	0
				Days	0
Formation :		PBTD : 0.0		Perf :	
				MW	0.0
				Visc	0.0
				PKR Depth : 0.0	

Activity at Report Time: TESTING BOPE

Start	End	Hrs	Activity Description
06:00	02:00	20.0	MOVE RIG 1.1 MILES TO LOCATION. 7 BED TRUCKS, 2 HAUL TRUCKS, 1 CRANE, 2 FORKLIFTS. RELEASE CRANE @ 15:00, TRUCKS @ 15:30. DERRICK IN THE AIR @ 16:00. 5 HANDS, 33 HOURS.
02:00	03:00	1.0	NU BOP. X/O HCR VALVE. RIG ON DAYWORK @ 02:00.
03:00	06:00	3.0	TESTED PIPE RAMS, BLIND RAMS, HCR, CHOKE VALVE, CHOKE LINE & MANIFOLD, KILL LINE VALVES TO 5000 PSI FOR 10 MINUTES. TESTED UPPER & LOWER KELLY COCKS, FLOOR & INSIDE BOP TO 5000 PSI FOR 10 MINUTES. TESTED ANNULAR PREVENTER TO 2500 PSI FOR 10 MINUTES. TESTED CASING TO 1500 PSI FOR 30 MINUTES. R/D TESTER. NO BLM REP ON LOCATION TO WITNESS TEST. FULL CREWS, NO ACCIDENTS. SAFETY MEETING - RIGGING UP W/WESTROC TRUCKING, TEST BOP. NOTIFIED JAMIE SPARGER\VERNAL BLM\BOP TEST\4-28-08\08:00.

05-01-2008 Reported By PAT CLARK/JIM LOUDERMILK

Daily Costs: Drilling	\$111,999	Completion	\$0	Daily Total	\$111,999
Cum Costs: Drilling	\$392,597	Completion	\$350	Well Total	\$392,947
MD	4,250	TVD	4,250	Progress	1,775
				Days	1
Formation :		PBTD : 0.0		Perf :	
				MW	8.5
				Visc	26.0
				PKR Depth : 0.0	

Activity at Report Time: DRILLING @ 4250'

Start	End	Hrs	Activity Description
06:00	08:30	2.5	HSM, R/U WEATHERFORD TRS. PU BHA AND DP, TAG CEMENT @ 2366'. R/D TRS.
08:30	09:00	0.5	SLIP & CUT 80' DRILL LINE, PRE-SPUD.
09:00	10:30	1.5	DRILL CEMENT/FLOAT EQUIP. FC @ 2430', FS @ 2475'. DRILL 10' TO 2485'.
10:30	11:00	0.5	DRILL TO 2491' & PERFORM 10.5 PPG EMW TEST, (270 PSI SPP). FUNCTIONED PIPE RAMS & HCR.
11:00	13:30	2.5	DRILL 2491'-2680', (12-18K WOB / 65 RPM-65MTR / 420 GPM), 94.5 FPH.
13:30	14:00	0.5	RIG SERVICE / SURVEY, 2 DEGREES @ 2604'.
14:00	04:30	14.5	DRILL 2680'-4150', (12-18K WOB / 65 RPM-65MTR / 420 GPM), 101.4 FPH.
04:30	05:00	0.5	WLS / 1.25 DEGREES @ 4075'.
05:00	06:00	1.0	DRILL 4150'-4250', (12-18K WOB / 65 RPM-65MTR / 420 GPM), 100 FPH. VIS 29 WT 8.9.

CREWS: FULL / NO INCIDENTS REPORTED / HSM: MAKING CONNECTIONS & PINCH POINTS.

FUEL: 7634 GAL. MUD LOGIC UNMANNED OPERATIONAL ON 4/30/2008 @ 00:00 HRS. 1 DAY.

06:00 06:00 24.0 SPUD 7 7/8" HOLE ON 4/30/2008 @ 11:00 HRS.

05-02-2008 Reported By JIM LOUDERMILK

Daily Costs: Drilling	\$23,625	Completion	\$0	Daily Total	\$23,625
Cum Costs: Drilling	\$416,222	Completion	\$350	Well Total	\$416,572
MD	6,150	TVD	6,150	Progress	1,900
				Days	2
Formation :		PBTD : 0.0		Perf :	
				MW	8.6
				Visc	27.0
				PKR Depth : 0.0	

Activity at Report Time: DRILLING @ 6150'

Start	End	Hrs	Activity Description
06:00	07:00	1.0	DRILL 4250'-4400', (12-18K WOB / 65 RPM-65MTR / 420 GPM), 150 FPH.
07:00	07:30	0.5	RIG SERVICE / FUNCTION PIPE RAMS & CHECK COM.
07:30	06:00	22.5	DRILL 4400'-6150', (15-22K WOB / 65 RPM-67MTR / 420 GPM), 77.8 FPH. VIS 29 WT 8.9.
CREWS: FULL / NO INCIDENTS REPORTED / HSM: TEAM WORK & PPE / BOTH CREWS HELD BOP DRILLS.			
FUEL: 6325 GAL. USED 1309 GAL. MUD LOGIC UNMANNED UNIT, 2 DAYS.			

05-03-2008 **Reported By** JIM LOUDERMILK

Daily Costs: Drilling	\$21,841	Completion	\$0	Daily Total	\$21,841
Cum Costs: Drilling	\$438,064	Completion	\$350	Well Total	\$438,414
MD	6,850	TVD	6,850	Progress	700
Days	3	MW	8.5	Visc	28.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0	

Activity at Report Time: DRILLING @ 6850'

Start	End	Hrs	Activity Description
06:00	13:30	7.5	DRILL 6150'-6540', (20-25K WOB / 65 RPM-67MTR / 420 GPM), 52 FPH.
13:30	14:00	0.5	RIG SERVICE / FUNCTION PIPE RAMS & CHECK COM.
14:00	19:00	5.0	DRILL 6540'-6667', (20-25K WOB / 65 RPM-67MTR / 420 GPM), 25.4 FPH.
19:00	19:30	0.5	PUMP PILL / DROP SURVEY.
19:30	22:00	2.5	TRIP OUT WITH BIT #1 / LD RMR'S & CHANGE OUT MOTORS / FUNCTIONED BLIND RAMS / CORRECT JOINT COUNT.
22:00	01:30	3.5	TRIP IN WITH BIT #2.
01:30	02:30	1.0	REAM 6547'-6667', (PRECAUTIONARY).
02:30	06:00	3.5	DRILL 6667'-6850', (12-18K WOB / 65 RPM-63MTR / 420 GPM), 52.2 FPH. VIS 30 WT 9.8.
CREWS: FULL / NO INCIDENTS REPORTED / HSM: TRIPPING & PINCH POINTS.			
FUEL: 5289 GAL. USED 1036 GAL. MUD LOGIC UNMANNED UNIT, 3 DAYS.			

05-04-2008 **Reported By** JIM LOUDERMILK

Daily Costs: Drilling	\$62,990	Completion	\$0	Daily Total	\$62,990
Cum Costs: Drilling	\$501,055	Completion	\$350	Well Total	\$501,405
MD	8,115	TVD	8,115	Progress	1,265
Days	4	MW	9.9	Visc	33.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0	

Activity at Report Time: DRILLING @ 8115'

Start	End	Hrs	Activity Description
06:00	06:30	0.5	DRILL 6850'-6875', (12-18K WOB / 65 RPM-63MTR / 420 GPM), 50 FPH.
06:30	07:00	0.5	RIG SERVICE / FUNCTION PIPE RAMS & CHECK COM.
07:00	06:00	23.0	DRILL 6875'-', (12-18K WOB / 65 RPM-63MTR / 420 GPM), 53.9 FPH. VIS 33 WT 10.5.
CREWS: FULL / NO INCIDENTS REPORTED / HSM: JOB FOCUS & RETURN TO WORK. BOTH CREWS HELD BOP DRILLS. FUEL: 3382 GAL. USED 1907 GAL. MUD LOGIC UNMANNED UNIT, 4 DAYS.			

05-05-2008 **Reported By** JIM LOUDERMILK

Daily Costs: Drilling	\$34,241	Completion	\$0	Daily Total	\$34,241
Cum Costs: Drilling	\$535,296	Completion	\$350	Well Total	\$535,646
MD	8,825	TVD	8,825	Progress	710
Days	5	MW	10.2	Visc	35.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0	

Activity at Report Time: DRILLING @ 8825'

Start	End	Hrs	Activity Description
06:00	13:00	7.0	DRILL 8115'-8320', (16-18K WOB / 65 RPM-63MTR / 420 GPM), 29.3 FPH.
13:00	13:30	0.5	RIG SERVICE / FUNCTION PIPE RAMS & CHECK COM.
13:30	06:00	16.5	DRILL 8320'-8825', (18-22K WOB / 65 RPM-63MTR / 420 GPM), 30.6 FPH. VIS 36 WT 10.7.
			CREWS: FULL / NO INCIDENTS REPORTED / HSM: TRAINING NEW EMPLOYEES.
			FUEL: 2305 GAL. USED 1517 GAL. MUD LOGIC UNMANNED UNIT, 5 DAYS.

05-06-2008 Reported By JIM LOUDERMILK

Daily Costs: Drilling	\$39,978	Completion	\$0	Daily Total	\$39,978
Cum Costs: Drilling	\$575,275	Completion	\$350	Well Total	\$575,625
MD	9,070	TVD	9,070	Progress	245
		Days	6	MW	10.8
		Visc	38.0		
Formation :	PBTD : 0.0	Perf :	PKR Depth : 0.0		

Activity at Report Time: LDDP.

Start	End	Hrs	Activity Description
06:00	13:30	7.5	DRILL 8825'-8980', (18-22K WOB / 65 RPM-63MTR / 420 GPM), 20.6 FPH.
13:30	14:30	1.0	MIX & PUMP PILL / DROP SURVEY.
14:30	18:00	3.5	TRIP OUT WITH BIT #2 / FUNCTION BLIND RAMS. CHECK SURVEY, MISS RUN.
18:00	21:00	3.0	CHANGE OUT MOTORS & PU BIT #3.
21:00	21:30	0.5	REAM 8930'-8980', (PRECAUTIONARY).
21:30	01:30	4.0	DRILL 8980'-9070' TD, (18-22K WOB / 65 RPM-63MTR / 420 GPM), 22.5 FPH. REACHED TD 5/6/2008 @ 01:30 HRS. NOTIFIED GEORGE ROSS & ERIK KLING, VIA EMAIL.
01:30	02:30	1.0	CBU / HSM WITH WEATHERFORD TRS & RU.
02:30	06:00	3.5	LDDP. VIS 38 WT 10.9. CREWS: FULL / NO INCIDENTS REPORTED / HSM: LDDP & PINCH POINTS.
			FUEL: 1215 GAL. USED 1090 GAL. MUD LOGIC UNMANNED UNIT, 6 DAYS. NOTIFIED JAMIE SPARGER, VIA VOICE MAIL, WITH THE VERNAL BLM FIELD OFFICE ON 5/5/2008 @ 09:00 HRS OF CASING RUN & CEMENT JOB TO TAKE PLACE ON 5/6/2008.

05-07-2008 Reported By JIM LOUDERMILK

Daily Costs: Drilling	\$46,775	Completion	\$136,654	Daily Total	\$183,429
Cum Costs: Drilling	\$622,050	Completion	\$137,004	Well Total	\$759,054
MD	9,070	TVD	9,070	Progress	0
		Days	7	MW	0.0
		Visc	0.0		
Formation :	PBTD : 0.0	Perf :	PKR Depth : 0.0		

Activity at Report Time: RDRT/NO COMPLETION

Start	End	Hrs	Activity Description
06:00	08:30	2.5	LDDP / BREAK KELLY & RETRIEVE WEAR BUSHING.
08:30	09:30	1.0	HSM WITH WEATHERFORD TRS & RU.
09:30	14:30	5.0	RAN WEATHERFORD MODEL 303E FLOAT SHOE, (1.50'), 1JT, (40.61'), OF 4.5", 11.6#, N80, LTC, R3 CASING AND WFORF MODEL 402E FLOAT COLLAR, (1.50'). FOLLOWED BY 222 JOINTS, (8943.67'), OF 4.5", 11.6#, N80, LTC, R3 CASING, 3 MARKER JOINTS, (51.80'), 1 MCH. (8.30') AND 1 LANDING JOINT W / HANGER, (16.00'). ALL 4.5", 11.6#, HCP-110, LTC CASING. TD OF 9070', LANDED @ 9063.88', FLOAT COLLAR @ 9020.27', WITH MARKERS @ 6420.84', 4223.05' & 24.80'. CHECK SPACE OUT FOR MCH WITH JOINT #224. LAND CASING WITH 64K ON HANGER.
14:30	15:30	1.0	CBU / HSM WITH SCHLUMBERGER & RU.
15:30	17:30	2.0	TEST LINES TO 5K. PUMP 20 BBL'S MUD FLUSH & 20 BBL'S OF FRESH WATER SPACER.

LEAD: 255 SKS OF "G" MIXED @ 11.5 PPG, 2.98 YLD + 10% D020 + .2% D046 + .2% D167 + .5% D065 + .125 LB/SK D130. TAIL: 1455 SKS OF 50/50 POZ"G" MIXED @ 14.1 PPG AND 1.29 YLD + .2% D020 + .1% D046 + .2% D065 + .2% D167 + .1% D013 FOR ADDITIVES. DSPL: 140 BBL'S OF FRESH WATER PUMPED @ 6 BPM. FULL MUD RETURNS THROUGHOUT THE JOB, BUMPED PLUG WITH 1000 PSI OVER FPIP OF 2350 PSI, FLOATS HELD BLEED BACK 1.5 BBL'S. CEMENT IN PLACE ON 5/6/2008 @ 17:30 HRS.

17:30	18:30	1.0 WAIT ON CEMENT / FMC REP TESTED PACK OFF TO 5K.
18:30	22:00	3.5 ND BOP. CLEAN MUD TANKS.
22:00	06:00	8.0 RDRT / PREPARE FOR TRUCKS.

CREWS: FULL / NO INCIDENTS REPORTED / HSM: LDDP, RUN CSG & CMT-PINCH POINTS & PRESSURIZED LINES. MUD LOGIC UNMANNED UNIT 7 DAYS, RELEASED ON 5/6/2008 @ 09:00.

WESTROC TRUCKING TO MOVE RIG 4.8 MILES FROM THE ECW 60-16 TO THE ECW 18-17 ON 5/7/2008 @ 07:00 HRS. TRANSFER 5 JTS, (201.93' NET), OF 4.5", 11.6#, N80, LTC R3 CASING, 1 LANDING JT & 1 MJ, (10.12' NET), OF 4.5", 11.6#, HCP110 LTC CASING AND 3300 GAL. DIESEL FROM THE ECW 60-16 TO THE ECW 18-17. TRANSFER APPROXIMATELY 1100 BBL'S OF 10.9 PPG MUD TO THE MUD STORAGE FACILITY & VARIOUS RIGS.

06:00	06:00	24.0 RELEASE RIG ON 5/6/2008 @ 22:00 HRS.
CASING POINT COST\$ 622,051		

05-10-2008		Reported By		MCCURDY	
Daily Costs: Drilling	\$0	Completion	\$39,504	Daily Total	\$39,504
Cum Costs: Drilling	\$622,050	Completion	\$176,508	Well Total	\$798,558
MD	9,070	TVD	9,070	Progress	0
Days	9	MW	0.0	Visc	0.0
Formation :		PBTD : 0.0		Perf :	
Activity at Report Time:		PKR Depth : 0.0			
Start	End	Hrs	Activity Description		
06:00	06:00	24.0	5-9-08 RU SCHLUMBERGER. LOG WITH RST/CBL/VDL/CCL/GR FROM PBTD TO 940'. CEMENT TOP ABOVE SURFACE CASING SHOE. RD SCHLUMBERGER.		

05-11-2008		Reported By		MCCURDY	
Daily Costs: Drilling	\$0	Completion	\$1,653	Daily Total	\$1,653
Cum Costs: Drilling	\$622,050	Completion	\$178,161	Well Total	\$800,211
MD	9,070	TVD	9,070	Progress	0
Days	8	MW	0.0	Visc	0.0
Formation :		PBTD : 0.0		Perf :	
Activity at Report Time: WO COMPLETION		PKR Depth : 0.0			
Start	End	Hrs	Activity Description		
06:00	06:00	24.0	NU 10M FRAC TREE. PRESSURE TESTED FRAC TREE & CASING TO 6500 PSIG. WO COMPLETION.		

06-05-2008		Reported By		JOE VIGIL	
Daily Costs: Drilling	\$0	Completion	\$48,136	Daily Total	\$48,136
Cum Costs: Drilling	\$622,050	Completion	\$226,297	Well Total	\$848,348
MD	9,070	TVD	9,070	Progress	0
Days	9	MW	0.0	Visc	0.0
Formation : MESAVERDE / WASATCH		PBTD : 0.0		Perf : 7807'-889'	
Activity at Report Time: FRAC UPR		PKR Depth : 0.0			
Start	End	Hrs	Activity Description		

06:00 06:00 24.0 MIRU CUTTERS WIRELINE & PERFORATE LPR FROM 8672'-73', 8686'-87', 8696'-97', 8710'-11', 8727'-28', 8744'-45', 8755'-56', 8779'-80', 8828'-29', 8840'-41', 8876'-77', 8894'-95', @ 3 SPF @ 120° PHASING. RDWL. MIRU SCHLUMBERGER, FRAC DOWN CASING WITH 165 GAL GYPTRON T-106, 5212 GAL 16# YF116ST PAD, 6311 GAL 16# YF116ST W/ 1# & 1.5#, 28692 GAL 16# YF116ST + W/ 99400 # 20/40 SAND @ 1-4 PPG. MTP 6544 PSIG. MTR 51.5 BPM. ATP 5497 PSIG. ATR 48.5 BPM. ISIP 2800 PSIG. RD SCHLUMBERGER.

RUWL SET 6K CFP AT 8650'. PERFORATE LPR FROM 8451'-53', 8476'-77', 8496'-97', 8537'-38', 8541'-42', 8559'-60', 8566'-67', 8593'-94', 8599'-00', 8609'-10', 8630'-31', @ 3 SPF @ 120° PHASING. RDWL. RU SCHLUMBERGER, FRAC DOWN CASING WITH 165 GAL GYPTRON T-106, 4578 GAL 16# YF116ST PAD, 6320 GAL 16# YF116ST W/ 1# & 1.5# SAND, 28456 GAL YF116ST + W/ 98200 # 20/40 SAND @ 1-4 PPG. MTP 6352 PSIG. MTR 50.5 BPM. ATP 5599 PSIG. ATR 47.5 BPM. ISIP 3100 PSIG. RD SCHLUMBERGER.

RUWL SET 6K CFP AT 8425'. PERFORATE MPR FROM 8156'-57', 8178'-79', 8196'-97', 8215'-16', 8227'-28', 8256'-57', 8299'-00', 8310'-11', 8329'-30', 8376'-77', 8386'-87', 8401'-02', @ 3 SPF @ 120° PHASING. RDWL. RU SCHLUMBERGER, FRAC DOWN CASING WITH 165 GAL GYPTRON T-106, 4556 GAL 16# YF116ST PAD, 8407 GAL 16# YF116ST W/ 1# & 1.5# SAND, 38764 GAL YF116ST + W/ 137900 # 20/40 SAND @ 1-5 PPG. MTP 6527 PSIG. MTR 51.5 BPM. ATP 5549 PSIG. ATR 48.5 BPM. ISIP 3650 PSIG. RD SCHLUMBERGER.

RUWL SET 6K CFP AT 8120'. PERFORATE MPR FROM 7914'-15', 7937'-38', 7943'-44', 7952'-53', 7964'-65', 8004'-05', 8016'-17', 8023'-24', 8031'-32', 8055'-56', 8069'-70', 8085'-86', @ 3 SPF @ 120° PHASING. RDWL. RU SCHLUMBERGER, FRAC DOWN CASING WITH 165 GAL GYPTRON T-106, 4153 GAL 16# YF116ST PAD, 7566 GAL 16# YF116ST W/ 1# & 1.5# SAND, 35754 GAL YF116ST + W/ 128600 # 20/40 SAND @ 1-5 PPG. MTP 6358 PSIG. MTR 51 BPM. ATP 5355 PSIG. ATR 51 BPM. ISIP 2330 PSIG. RD SCHLUMBERGER.

RUWL SET 6K CFP AT 7885'. PERFORATE MPR FROM 7807'-09', 7824'-26', 7835'-37', 7845'-47', 7855'-57', 7865'-67', @ 3 SPF @ 120° PHASING. RDWL. RU SCHLUMBERGER, FRAC DOWN CASING WITH 165 GAL GYPTRON T-106, 3096 GAL 16# YF116ST PAD, 7149 GAL 16# YF116ST W/ 1# & 1.5# SAND, 33897 GAL YF116ST + W/ 121000 # 20/40 SAND @ 1-5 PPG. MTP 6440 PSIG. MTR 51.5 BPM. ATP 4663 PSIG. ATR 49.5 BPM. ISIP 2400 PSIG. RD SCHLUMBERGER. SDFN.

06-06-2008 Reported By JOE VIGIL

Daily Costs: Drilling \$0 Completion \$3,150 Daily Total \$3,150

Cum Costs: Drilling \$622,050 Completion \$229,447 Well Total \$851,498

MD 9,070 TVD 9,070 Progress 0 Days 10 MW 0.0 Visc 0.0

Formation : MESAVERDE / PBTB : 0.0 Perf : 6821'-8895' PKR Depth : 0.0
WASATCH

Activity at Report Time: FRAC

Start	End	Hrs	Activity Description
06:00	06:00	24.0	RUWL. SET 6K CFP AT 7780'. PERFORATE MPR FROM 7553'-54', 7598'-99', 7608'-09', 7638'-39', 7649'-50', 7663'-64', 7692'-93', 7706'-07', 7714'-15', 7735'-36', 7748'-49', 7754'-55' @ 3 SPF @ 120° PHASING. RDWL. RU SCHLUMBERGER, FRAC DOWN CASING WITH 165 GAL GYPTRON T-106, 3120 GAL 16# YF116ST PAD, 9326 GAL 16# YF116ST W/1# & 1.5# 20/40 SAND, 42238 GAL YF116ST+ W/150200# 20/40 SAND @ 1-5 PPG. MTP 6260 PSIG. MTR 51 BPM. ATP 4779 PSIG. ATR 48 BPM. ISIP 2700 PSIG. RD SCHLUMBERGER.

RUWL. SET 6K CFP AT 7515'. PERFORATE UPR FROM 7204'-05', 7229'-30', 7239'-40', 7266'-67', 7286'-87', 7293'-94', 7314'-15', 7340'-41', 7383'-84', 7430'-31', 7443'-44', 7494'-95' @ 3 SPF @ 120° PHASING. RDWL. RU SCHLUMBERGER, FRAC DOWN CASING WITH 165 GAL GYPTRON T-106, 3108 GAL 16# YF116ST PAD, 10703 GAL 16# YF116ST W/1# & 1.5# 20/40 SAND, 50760 GAL YF116ST+ W/182000# 20/40 SAND @ 1-5 PPG. MTP 6356 PSIG. MTR 51.5 BPM. ATP 4508 PSIG. ATR 48.5 BPM. ISIP 2700 PSIG. RD SCHLUMBERGER.

RUWL. SET 6K CFP AT 7120'. PERFORATE UPR FROM 6821'-22', 6836'-37', 6850'-51', 6864'-65', 6882'-83', 6906'-07', 6917'-18', 7030'-31', 7039'-40', 7051'-52', 7083'-84', 7093'-94', @ 3 SPF @ 120° PHASING. RDWL. RU SCHLUMBERGER, FRAC DOWN CASING WITH 165 GAL GYPTRON T-106, 3315 GAL 16# YF116ST PAD, 12604 GAL 16# YF116ST W/1# & 1.5# 20/40 SAND, 55754 GAL YF116ST+ W/200100# 20/40 SAND @ 1-5 PPG. MTP 6230 PSIG. MTR 52 BPM. ATP 4208 PSIG. ATR 49 BPM. ISIP 2000 PSIG. RD SCHLUMBERGER.

06-07-2008 Reported By JOE VIGIL

Daily Costs: Drilling	\$0	Completion	\$480,088	Daily Total	\$480,088
Cum Costs: Drilling	\$622,050	Completion	\$709,535	Well Total	\$1,331,586

MD	9,070	TVD	9,070	Progress	0	Days	11	MW	0.0	Visc	0.0
-----------	-------	------------	-------	-----------------	---	-------------	----	-----------	-----	-------------	-----

Formation : MESAVERDE /	PBTD : 0.0	Perf : 5134'-8895'	PKR Depth : 0.0
WASATCH			

Activity at Report Time: PREP TO MIRUSU

Start	End	Hrs	Activity Description
-------	-----	-----	----------------------

06:00	06:00	24.0	RUWL. SET 6K CFP AT 6760'. PERFORATE NH FROM 6466'-67', 6487'-88', 6515'-16', 6590'-93', 6639'-40', 6674'-75', 6710'-11', 6721'-22', 6728'-29', 6738'-39' @ 3 SPF @ 120° PHASING. RDWL. RU SCHLUMBERGER, FRAC DOWN CASING WITH 165 GAL GYPTRON T-106, 3085 GAL 16# YF116ST PAD, 7135 GAL 16# YF116ST W/1# & 1.5# 20/40 SAND, 33460 GAL YF116ST+ W/120400# 20/40 SAND @ 1-5 PPG. MTP 5222 PSIG. MTR 51.5 BPM. ATP 4540 PSIG. ATR 48.5 BPM. ISIP 2500 PSIG. RD SCHLUMBERGER.
-------	-------	------	--

RUWL. SET 6K CFP AT 6350'. PERFORATE BA FROM 6094'-95', 6115'-16', 6131'-32', 6143'-44', 6157'-60', 6231'-32', 6242'-43', 6398'-99', 6312'-13', 6317'-18' @ 3 SPF @ 120° PHASING. RDWL. RU SCHLUMBERGER, FRAC DOWN CASING W/ 3103 GAL 16# YF116ST PAD, 6328 GAL 16# YF116ST W/1# & 1.5# 20/40 SAND, 28222 GAL YF116ST+ W/97500# 20/40 SAND @ 1-4 PPG. MTP 5693 PSIG. MTR 52 BPM. ATP 4126 PSIG. ATR 48 BPM. ISIP 2000 PSIG. RD SCHLUMBERGER.

RUWL. SET 6K CFP AT 6070'. PERFORATE BA FROM 5883'-85', 5890'-92', 5954'-55', 5967'-69', 5977'-78', 5986'-87', 6017'-18', 6041'-42', 6049'-50' @ 3 SPF @ 120° PHASING. RDWL. RU SCHLUMBERGER, FRAC DOWN CASING W/3082 GAL 16# YF116ST PAD, 7356 GAL 16# YF116ST W/1# & 1.5# 20/40 SAND, 29882 GAL YF116ST+ W/102400# 20/40 SAND @ 1-4 PPG. MTP 4871 PSIG. MTR 52 BPM. ATP 3556 PSIG. ATR 49 BPM. ISIP 1700 PSIG. RD SCHLUMBERGER.

RUWL. SET 6K CFP AT 5832'. PERFORATE CA FROM 5611'-12', 5617'-18', 5634'-35', 5643'-44', 5714'-15', 5723'-24', 5742'-43', 5784'-85', 5804'-06', 5813'-15' @ 3 SPF @ 120° PHASING. RDWL. RU SCHLUMBERGER, FRAC DOWN CASING W/3105 GAL 16# YF116ST PAD, 7356 GAL 16# DELTA 200 W/1# & 1.5# 20/40 SAND, 26709 GAL YF116ST+ W/89700# 20/40 SAND @ 1-4 PPG. MTP 5111 PSIG. MTR 51 BPM. ATP 3549 PSIG. ATR 48 BPM. ISIP 1860 PSIG. RD SCHLUMBERGER.

RUWL. SET 6K CFP AT 5550'. PERFORATE CA FROM 5426'-28', 5438'-40', 5447'-49', 5461'-63', 5467'-69', 5517'-19' @ 3 SPF @ 120° PHASING. RDWL. RU SCHLUMBERGER, FRAC DOWN CASING W/3968 GAL 16# YF116ST PAD, 9465 GAL 16# YF116ST W/1# & 1.5# 20/40 SAND, 34489 GAL YF116ST+ W/119900# 20/40 SAND @ 1-4 PPG. MTP 4946 PSIG. MTR 51.5 BPM. ATP 3605 PSIG. ATR 49 BPM. ISIP 2100 PSIG. RD SCHLUMBERGER.

RUWL. SET 6K CBP AT 5350'. PERFORATE CA FROM 5245'-46', 5260'-61', 5270'-71', 5282'-84', 5290'-93', 5299'-00', 5307'-08' & 5316'-18' @ 3 SPF @ 120° PHASING. RDWL. RU SCHLUMBERGER, FRAC DOWN CASING W/3135 GAL 16# YF116ST PAD, 9462 GAL 16# YF116ST W/1# & 1.5# 20/40 SAND, 30453 GAL YF116ST+ W/106100# 20/40 SAND @ 1-4 PPG. MTP 5097 PSIG. MTR 53.5 BPM. ATP 3648 PSIG. ATR 50 BPM. ISIP 2400 PSIG. RD SCHLUMBERGER.

RUWL. SET 6K CBP AT 5208'. PERFORATE PP FROM 5134'-35', 5146'-47', 5163'-65', 5171'-73', 5178'-80', 5186'-90' @ 3 SPF @ 120° PHASING. RDWL. RU SCHLUMBERGER, FRAC DOWN CASING W/3097 GAL 16# YF116ST PAD, 9452 GAL 16# YF116ST W/1# & 1.5# 20/40 SAND, 32937 GAL YF116ST+ W/113600# 20/40 SAND @ 1-4 PPG. MTP 5122 PSIG. MTR 51.5 BPM. ATP 3866 PSIG. ATR 49 BPM. ISIP 2500 PSIG. RD SCHLUMBERGER.

RUWL. SET 6K CBP AT 5022'. RDWL. SDFN.

06-11-2008 Reported By HISLOP

Daily Costs: Drilling	\$0	Completion	\$33,987	Daily Total	\$33,987
Cum Costs: Drilling	\$622,050	Completion	\$743,522	Well Total	\$1,365,573

MD 9.070 TVD 9.070 Progress 0 Days 12 MW 0.0 Visc 0.0

Formation : MESAVERDE / PBTD : 0.0 Perf : 5134'-8895' PKR Depth : 0.0
WASATCH

Activity at Report Time: CLEAN OUT AFTER FRAC

Start	End	Hrs	Activity Description
06:00	06:00	24.0	SICP 0 PSIG. MIRUSU. ND TREE. NU BOP. RIH W/BIT & PUMP OFF SUB TO 5022'. RU TO DRILL PLUGS. SDFN.

06-12-2008 Reported By HISLOP

Daily Costs: Drilling	\$0	Completion	\$55,507	Daily Total	\$55,507
Cum Costs: Drilling	\$622,050	Completion	\$799,029	Well Total	\$1,421,080

MD 9.070 TVD 9.070 Progress 0 Days 13 MW 0.0 Visc 0.0

Formation : MESAVERDE / PBTD : 0.0 Perf : 5134'-8895' PKR Depth : 0.0
WASATCH

Activity at Report Time: FLOW TEST

Start	End	Hrs	Activity Description
06:00	06:00	24.0	SICP 0 PSIG. CLEANED OUT & DRILLED OUT PLUGS @ 5022', 5208', 5350', 5550', 5832', 6070', 6350', 6760', 7120', 7515', 7780', 7885', 8120', 8425' & 8650'. RIH. CLEANED OUT TO' PBTD @ 9020'. LANDED TUBING @ 6805' KB. ND BOP. NU TREE. PUMPED OFF BIT & SUB. RDMOSU.

FLOWED 10 HRS. 24/64" CHOKE. FTP 950 PSIG. CP 1200 PSIG. 69 FPH. RECOVERED 821 BLW. 15579 BLWTR.

TUBING DETAIL LENGTH

PUMP OFF BIT SUB .91'

1 JT 2-3/8" 4.7# L-80 TBG 32.78'

XN NIPPLE 1.30'

206 JTS 2-3/8" 4.7# L-80 TBG 6754.34'

BELOW KB 16.00'

LANDED @ 6805.33' KB

06-13-2008 Reported By HISLOP

Daily Costs: Drilling	\$0	Completion	\$55,507	Daily Total	\$55,507
Cum Costs: Drilling	\$622,050	Completion	\$854,536	Well Total	\$1,476,587

MD 9.070 TVD 9.070 Progress 0 Days 14 MW 0.0 Visc 0.0

Formation : MESAVERDE / PBTD : 9020.0 Perf : 5134'-8895' PKR Depth : 0.0
WASATCH

Activity at Report Time: FLOW TEST TO SALES/INITIAL PRODUCTION-GAS

Start	End	Hrs	Activity Description
06:00	06:00	24.0	FLOWED 24 HRS. 24/64" CHOKE. FTP 850 PSIG. CP 1100 PSIG. 60 BFPH. RECOVERED 1577 BLW. 16002 BLWTR. 0 MCFD RATE.

INITIAL PRODUCTION. TURNED TO GAS SALES. SITP 850 & SICP 1150 PSIG. TURNED WELL TO QUESTAR SALES AT 01:00 PM, 6/12/08. FLOWING 120 MCFD RATE ON 24/64" POS CK. STATIC 325.

06-14-2008 Reported By HISLOP

Daily Costs: Drilling	\$0	Completion	\$5,285	Daily Total	\$5,285
Cum Costs: Drilling	\$622,050	Completion	\$859,821	Well Total	\$1,481,872

MD 9,070 TVD 9,070 Progress 0 Days 15 MW 0.0 Visc 0.0

Formation : MESAVERDE / PBTB : 9020.0 Perf : 5134'-8895' PKR Depth : 0.0
WASATCH

Activity at Report Time: FLOW TEST TO SALES

Start	End	Hrs	Activity Description
06:00	06:00	24.0	FLOWED 24 HRS. 16/64" CHOKE. FTP 1000 PSIG. CP 1450 PSIG. 22 BFPH. RECOVERED 657 BLW. 15345 BLWTR. 266 MCFD RATE.

FLOWED 128 MCF, 5 BO/BC & 1255 BW IN 24 HRS ON 24/64" CHOKE, TP 925 PSIG, CP 1050 PSIG.

06-15-2008 Reported By HISLOP

Daily Costs: Drilling	\$0	Completion	\$2,765	Daily Total	\$2,765
Cum Costs: Drilling	\$622,050	Completion	\$862,586	Well Total	\$1,484,637

MD 9,070 TVD 9,070 Progress 0 Days 16 MW 0.0 Visc 0.0

Formation : MESAVERDE / PBTB : 9020.0 Perf : 5134'-8895' PKR Depth : 0.0
WASATCH

Activity at Report Time: FLOW TESTING

Start	End	Hrs	Activity Description
06:00	06:00	24.0	FLOWED THROUGH TEST UNIT 24 HRS. 20/64" CHOKE. FTP 850 PSIG. CP 2000 PSIG. 38 BFPH. RECOVERED 848 BLW. 14505 BLWTR. 255 MCFD RATE.

FLOWED 166 MCF, 5 BO/BC & 1255 BW IN 24 HRS ON 24/64" CHOKE, TP 890 PSIG, CP 1590 PSIG.

06-16-2008 Reported By HISLOP

Daily Costs: Drilling	\$0	Completion	\$2,765	Daily Total	\$2,765
Cum Costs: Drilling	\$622,050	Completion	\$865,351	Well Total	\$1,487,402

MD 9,070 TVD 9,070 Progress 0 Days 17 MW 0.0 Visc 0.0

Formation : MESAVERDE / PBTB : 9020.0 Perf : 5134'-8895' PKR Depth : 0.0
WASATCH

Activity at Report Time: FLOW TEST TO SALES

Start	End	Hrs	Activity Description
06:00	06:00	24.0	FLOW 24 HRS. 20/64" CHOKE. FTP 850 PSIG. CP 2150 PSIG. 30 BFPH. RECOVERED 782 BLW. 13723 BLWTR. 372 MCFD RATE.

FLOWED 202 MCF, 7 BO/BC & 905 BW IN 24 HRS ON 24/64" CHOKE, TP 840 PSIG, CP 2075 PSIG.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-47045
2. NAME OF OPERATOR: EOG Resources, Inc.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 1060 East Highway 40 CITY Vernal STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: 655' FNL & 625' FEL 40.041408 LAT 109.324756 LON QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENE 16 9S 23E S		8. WELL NAME and NUMBER: East Chapita 60-16
PHONE NUMBER: (435) 781-9145		9. API NUMBER: 43-047-39150
		10. FIELD AND POOL, OR WILDCAT: Natural Buttes/Wasatch/Mesaverde
		COUNTY: Uintah
		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>Site Facility Diagram</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Attached please find a site facility diagram.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY

NAME (PLEASE PRINT) Mickenzie Thacker	TITLE Operations Clerk
SIGNATURE <i>Mickenzie Thacker</i>	DATE 7/8/2008


(This space for State use only)

RECEIVED

JUL 14 2008

DIV. OF OIL, GAS & MINING

Geogresources Site Facility Diagram



Well Name: EAST CHAPITA 60-16
1/4 1/4:NE/NE Sec: 16 T:9S R:23E
County:UINTAH State:UTAH
Lease: ML-47045

Site facility diagrams & site security plans are located at the Vernal office in Vernal, Utah. The office is located at 1060 East Hwy 40 and normal business hours are 7:00 a.m. to 4:30 p.m. Mon -Thurs and 7:00 a.m. to 1:00 p.m. Fridays.

Valve	Production Phase	Sales Phase	Water Drain
PV	O	SC	SC
LV	SC	O	SC
WD	SC	SC	O

DATED 7/8/2008

Abbreviations

AM = Allocation Meter
 AR = Access Road
 CHT = Chemical Tank
 COMP = Compressor
 CON = Condensor
 CT = Condensate Tank
 DL = Dump Line
 EP = Electrical Panel
 ET = Emergency Tank
 FW = Firewall
 LACT = LACT Unit
 LH = Line Heater
 LV = Load Valve
 MAN = Manifold
 MB = Methanol Bath
 O = Open
 PL = Production Line
 PP = Power Pole
 PT = Propane Tank
 PU = Pumping Unit
 PV = Production Valve
 PW = Produced Water
 RL = Recycle Line
 RP = Recycle Pump
 RV = Recycle Valve
 SC = Sealed Closed
 SGS = Sales Gas Scrubber
 SL = Sales Line
 SM = Sales Meter
 SO = Sealed Open
 SP = Separator
 SV = Sales Valve
 T = Treater
 TP = Trace Pump
 WD = Water Drain
 WDP = Water Disposal Pump
 WFP = Water Flood Pump
 WH = Wellhead


----- = Buried Line
 _____ = Unburied Line

▽ = Meter Display

□ = Meter Tube

○ = Production Valve

× = Valve



STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☐ FORM 8
(highlight changes)

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL: OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> DRY <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-47045
b. TYPE OF WORK: NEW WELL <input checked="" type="checkbox"/> HORIZ. LATS. <input type="checkbox"/> DEEP-EN <input type="checkbox"/> RE-ENTRY <input type="checkbox"/> DIFF. RESVR. <input type="checkbox"/> OTHER _____		6. IF INDIAN, ALLOTTEE OR TRIBE NAME .
2. NAME OF OPERATOR: EOG Resources, Inc.		7. UNIT or CA AGREEMENT NAME
3. ADDRESS OF OPERATOR: 600 17th St., Suite 1000N CITY Denver STATE CO ZIP 80202		8. WELL NAME and NUMBER: East Chapita 60-16
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 655' FNL & 625' FEL 40.041408 LAT 109.324756 LON AT TOP PRODUCING INTERVAL REPORTED BELOW: Same AT TOTAL DEPTH: Same		9. API NUMBER: 43-047-39150
10 FIELD AND POOL, OR WILDCAT Natural Buttes/Wasatch/Mesaverde		11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENE 16 9S 23E S
12. COUNTY Uintah		13. STATE UTAH

14. DATE SPUDDED: 4/5/2008	15. DATE T.D. REACHED: 5/6/2008	16. DATE COMPLETED: 6/12/2008	ABANDONED <input type="checkbox"/> READY TO PRODUCE <input checked="" type="checkbox"/>	17. ELEVATIONS (DF, RKB, RT, GL): 4965' NAT GL
18. TOTAL DEPTH: MD 9,070 TVD	19. PLUG BACK T.D.: MD 9,020 TVD	20. IF MULTIPLE COMPLETIONS, HOW MANY? *		21. DEPTH BRIDGE MD PLUG SET: TVD
22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each) RST/CBL/CCL/DR/GR, Temp.			23. WAS WELL CORED? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit analysis) WAS DST RUN? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit report) DIRECTIONAL SURVEY? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit copy)	

24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
12-1/4	9-5/8 J-55	36.0	0	2,475		800			
7-7/8	4-1/2 N-80	11.6	0	9,064		1710			

25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
2-3/8	6,805							

26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
(A) Wasatch/Mesaverde	5,134	8,895			8,672 8,895		3	Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(B)					8,451 8,631		3	Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(C)					8,156 8,402		3	Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(D)					7,914 8,086		3	Open <input type="checkbox"/> Squeezed <input type="checkbox"/>

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
8672-8895	40,380 GALS GELLED WATER & 99,400# 20/40 SAND
8451-8631	39,519 GALS GELLED WATER & 98,200# 20/40 SAND
8156-8402	51,892 GALS GELLED WATER & 137,900# 20/40 SAND

29. ENCLOSED ATTACHMENTS:

- ☐ ELECTRICAL/MECHANICAL LOGS ☐ GEOLOGIC REPORT ☐ DST REPORT ☐ DIRECTIONAL SURVEY
☐ SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION ☐ CORE ANALYSIS ☐ OTHER: _____

30. WELL STATUS:

Producing

RECEIVED

JUL 21 2008

31. INITIAL PRODUCTION

INTERVAL A (As shown in item #26)

DATE FIRST PRODUCED: 6/12/2008	TEST DATE: 7/3/2008	HOURS TESTED: 24	TEST PRODUCTION RATES: →	OIL – BBL: 20	GAS – MCF: 736	WATER – BBL: 100	PROD. METHOD: Flows
CHOKE SIZE: 12/64"	TBG. PRESS. 1,900	CSG. PRESS. 2,000	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS: Producing

INTERVAL B (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

INTERVAL C (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

INTERVAL D (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof. Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
Wasatch/Mesaverde	5,134	8,895		Green River	1,775
				Mahogany	2,418
				Uteland Butte	4,515
				Wasatch	4,656
				Chapita Wells	5,235
				Buck Canyon	5,901
				Price River	6,834
				Middle Price River	7,630
				Lower Price River	8,390
				Sego	8,929

35. ADDITIONAL REMARKS (Include plugging procedure)

See attached page for additional information.

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) Mary A. MaestasTITLE Regulatory AssistantSIGNATURE Mary A. MaestasDATE 7/18/2008

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

** ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

East Chapita 60-16 - ADDITIONAL REMARKS (CONTINUED):

27. PERFORATION RECORD

7807-7867	3/spf
7553-7755	3/spf
7204-7495	3/spf
6821-7094	3/spf
6466-6739	3/spf
6094-6318	3/spf
5883-6050	3/spf
5611-5815	3/spf
5426-5519	3/spf
5245-5318	3/spf
5134-5190	3/spf

28. ACID, FRACTURE TREATMENT, CEMENT SQUEEZE, ETC.

7914-8086	47,638 GALS GELLED WATER & 128,600# 20/40 SAND
7807-7867	44,307 GALS GELLED WATER & 121,000# 20/40 SAND
7553-7755	54,849 GALS GELLED WATER & 150,200# 20/40 SAND
7204-7495	64,736 GALS GELLED WATER & 182,000# 20/40 SAND
6821-7094	71,838 GALS GELLED WATER & 200,100# 20/40 SAND
6466-6739	43,845 GALS GELLED WATER & 120,400# 20/40 SAND
6094-6318	37,653 GALS GELLED WATER & 97,500# 20/40 SAND
5883-6050	40,320 GALS GELLED WATER & 102,400# 20/40 SAND
5611-5815	37,170 GALS GELLED WATER & 89,700# 20/40 SAND
5426-5519	47,922 GALS GELLED WATER & 119,900# 20/40 SAND
5245-5318	43,050 GALS GELLED WATER & 106,100# 20/40 SAND
5134-5190	45,486 GALS GELLED WATER & 113,600# 20/40 SAND

Perforated the Lower Price River from 8672-73', 8686-87', 8696-97', 8710-11', 8727-28', 8744-45', 8755-56', 8779-80', 8828-29', 8840-41', 8876-77', 8894-95' w/ 3 spf.

Perforated the Lower Price River from 8451-53', 8476-77', 8496-97', 8537-38', 8541-42', 8559-60', 8566-67', 8593-94', 8599-8600', 8609-10', 8630-31' w/ 3 spf.

Perforated the Middle Price River from 8156-57', 8178-79', 8196-97', 8215-16', 8227-28', 8256-57', 8299-8300', 8310-11', 8329-30', 8376-77', 8386-87', 8401-02' w/ 3 spf.

Perforated the Middle Price River from 7914-15', 7937-38', 7943-44', 7952-53', 7964-65', 8004-05', 8016-17', 8023-24', 8031-32', 8055-56', 8069-70', 8085-86' w/ 3 spf.

Perforated the Middle Price River from 7807-09', 7824-26', 7835-37', 7845-47', 7855-57', 7865-67' w/ 3 spf.

Perforated the Middle Price River from 7553-54', 7598-99', 7608-09', 7638-39', 7649-50', 7663-64', 7692-93', 7706-07', 7714-15', 7735-36', 7748-49', 7754-55' w/ 3 spf.

Perforated the Upper Price River from 7204-05', 7229-30', 7239-40', 7266-67', 7286-87', 7293-94', 7314-15', 7340-41', 7383-84', 7430-31', 7443-44', 7494-95' w/ 3 spf.

Perforated the Upper Price River from 6821-22', 6836-37', 6850-51', 6864-65', 6882-83', 6906-07', 6917-18', 7030-31', 7039-40', 7051-52', 7083-84', 7093-94' w/ 3 spf.

Perforated the North Horn from 6466-67', 6487-88', 6515-16', 6590-93', 6639-40', 6674-75', 6710-11', 6721-22', 6728-29', 6738-39' w/ 3 spf.

Perforated the Ba from 6094-95', 6115-16', 6131-32', 6143-44', 6157-60', 6231-32', 6242-43', 6298-99', 6312-13', 6317-18' w/ 3 spf.

Perforated the Ba from 5883-85', 5890-92', 5954-55', 5967-69', 5977-78', 5986-87', 6017-18', 6041-42', 6049-50' w/ 3 spf.

Perforated the Ca from 5611-12', 5617-18', 5634-35', 5643-44', 5714-15', 5723-24', 5742-43', 5784-85', 5804-06', 5813-15' w/ 3 spf.

Perforated the Ca from 5426-28', 5438-40', 5447-49', 5461-63', 5467-69', 5517-19' w/ 3 spf.

Perforated the Ca from 5245-46', 5260-61', 5270-71', 5282-84', 5290-93', 5299-5300', 5307-08', 5316-18' w/ 3 spf.

Perforated the Pp from 5134-35', 5146-47', 5163-65', 5171-73', 5178-80', 5186-90' w/ 3 spf.

FORM 7

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____	5. LEASE DESIGNATION AND SERIAL NUMBER: ML-47045
2. NAME OF OPERATOR: EOG Resources, Inc.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 1060 East Highway 40 Vernal UT 84078	7. UNIT or CA AGREEMENT NAME:
PHONE NUMBER: (435) 781-9145	8. WELL NAME and NUMBER: East Chapita 60-16
4. LOCATION OF WELL FOOTAGES AT SURFACE: 655' FNL & 625' FEL 40.041408 LAT 109.324756 LON	9. API NUMBER: 43-047-39150
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENE 16 9S 23E S	10. FIELD AND POOL, OR WILDCAT: Natural Buttes/Wasatch/Mesaverde

COUNTY: Uintah

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input checked="" type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

All material, debris, trash, and junk was removed from the location. The reserve pit was reclaimed. Stockpiled topsoil was spread over the pit area and broadcast seeded with the prescribed seed mixture. The seeded area was then walked down with a cat. Interim reclamation was completed in November 2008.

NAME (PLEASE PRINT) Mickenzie Thacker TITLE Operations Clerk
SIGNATURE *Mickenzie Thacker* DATE 1/14/2009

(This space for State use only)

RECEIVED

JAN 20 2009

DIV. OF OIL, GAS & MINING

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-47045
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: EOG Resources, Inc.		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 600 17th Street, Suite 1000 N , Denver, CO, 80202		8. WELL NAME and NUMBER: E CHAPITA 60-16
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0655 FNL 0625 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENE Section: 16 Township: 09.0S Range: 23.0E Meridian: S		9. API NUMBER: 43047391500000
9. FIELD and POOL or WILDCAT: NATURAL BUTTES		COUNTY: UINTAH
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 4/9/2012	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: Measurement variance propd
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:			
<input type="checkbox"/> SPUD REPORT Date of Spud:			
<input type="checkbox"/> DRILLING REPORT Report Date:			


12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
 EOG Resources, Inc. respectfully requests authorization to measure and allocate produced gas, condensate and water production as per the attached proposal.

Approved by the
Utah Division of
Oil, Gas and Mining


Date: May 11, 2012

By: *Derek Duff*

NAME (PLEASE PRINT) Mickenzie Gates	PHONE NUMBER 435 781-9145	TITLE Operations Clerk
SIGNATURE N/A	DATE 4/9/2012	



East Chapita 47-16 location, 16 central facility for Section 16 All official measurement of gas, oil, and water will occur on this location







EOG Resources, Inc.
1060 E Hwy 40
Vernal, Utah 84078

FedEx
7933 4391 7041

March 14, 2012

Division of Natural Resources
Utah Division of Oil, Gas, and Mining
Attn: Dustin Doucet, Randy Thackery
1594 West North Temple, Suite 1210
Salt Lake City, UT 84116

RE: Central Facility - Gathering System
Hydrocarbon Measurement Proposal
Section 16 T9S R23E
Uintah County, Utah

Gentlemen:

EOG Resources has submitted a proposal to the School and Institutional Trust Land Administration (SITLA) to install a Central Production Facility / Gathering System for Lease ML-47045. The facility will be located in the SWNE of Section 16, Township 09 South, Range 23 East, on an expanded East Chapita Wells (ECW) 47-16 well location. As you are aware, we have been producing a couple of the wells (ECW 103-16 and ECW 106-16) in section 16 utilizing gas lift operations to enhance production from the wells and have been encouraged with the results of that operation. Based on that fact, we intend to incorporate gas compression into Central Production Facility where we can process the gas, compress it and then send dry gas back to the wells for enhanced recovery via gas lift operations. All of the gas that we use for gas lift operations will be pulled out of the gathering system prior to the measurement point at the Central Facility. We believe that by moving our operations to a central facility, we can reduce air emissions, lower our operating costs (eliminating water hauling by pumping the water to the Coyote disposal facility located in Section 16), enhance our production and ultimately extend the life of the wells. At this time, we intend to measure all production from Lease ML-47045 at the central facility except for the production from ECW 59-16 well which will be measured on location utilizing the existing orifice meter for gas measurement and tank gauging for condensate and water measurement. Currently, the ECW 59-16 well is the only well in Section 16 that is located north of Coyote Wash and we would have to cross the wash to bring the well into the central facility. Eventually, as we continue to develop the lease we would bring the ECW 59-16 well into the central facility. At this time, we intend to leave the existing separator / dehydrator units on location in order to test our wells.

Therefore, EOG Resources would like to propose the following methods to measure the gas, condensate and water production from the aforementioned lease (except for the ECW 59-16) and



EOG Resources, Inc.
1060 E Hwy 40
Vernal, Utah 84078

the methods that we would like to use to measure and allocate production back to the remaining producing wells in the lease.

Gas Measurement – all gas leaving the lease from the central facility will be measured using an electronic flow meter (EFM) with orifice plate that is compliant with American Gas Association No. 3 (AGA) standards and State of Utah Regulations (R649-2-8). This meter will be calibrated on a quarterly basis.

Allocation Method – In an effort to reduce emissions, we intend to produce the wells directly into the gathering system. At least initially, we intend to leave the existing Separator / Dehydrator unit in place and utilize the existing EFM to test the wells on a quarterly basis. This will allow us to allocate production back to the individual wells based on well tests. Each well test will be run for a minimum of 24 hours. Therefore, we propose to allocate gas production to each well by totalizing the results of the well tests for every well and then utilize the results of each individual well to determine a percentage of the total that each well contributes to the total. We will take that percentage for each well and multiply it times the total production that is measured leaving the lease at the central facility on a daily basis. That gas volume will be allocated back to each well and will be reported on a monthly basis.

Gas Lift Operations – Every well in the lease will be evaluated on a case by case basis as to the viability to add gas lift operations to the well. We would like to propose, that for each well that we decide to convert to gas lift or the wells where we have already installed gas lift operations, to measure the injected gas via an EFM (orifice or v-cone) meter at the well site. Therefore, for each well that has had gas lift installed, the volume used for the percentage calculation for allocation to each well will be determined by subtracting the injected volume (per 24 hour period) from the produced volume that was determined during the well test for each well.

Oil / Condensate / Water Measurement – all condensate produced will be sold at the central facility via a Lease Automatic Custody Transfer (LACT) meter. The LACT meter will be proven on a quarterly basis. All water produced will be measured by a master (turbine) meter at the central facility prior to entering the pipeline that goes to the Coyote Saltwater Disposal Facility that is located within the lease boundary.

Allocation Method – We intend to install turbine meters on the dumps in the existing Separator / Dehydrator unit at each well so that we can accurately measure the condensate and water production from each well during the well tests. Therefore, we propose to allocate condensate and water production to each well by totalizing the results of the well tests for every well and then utilize the results of each individual well to determine a percentage of the total that each well contributes to the total. We will take that condensate percentage from each well and multiply it times the total condensate sold at the central facility per month for the allocated condensate production for each well and take the water percentage from each well and multiply it times water volume that is measured per month via the master meter that is located at the central facility for the allocated water production for each well. Those condensate and water volumes will be allocated back to each well and will be reported on a monthly basis.



EOG Resources, Inc.
1060 E Hwy 40
Vernal, Utah 84078

I look forward to hearing from you soon regarding our proposal. If you need any other information from me, I can be reached at (435) 781-9100 (office) or (435) 828-8236 (cell).

Sincerely,

A handwritten signature in dark ink, appearing to read "Ed Forsman", written over a horizontal line.

Ed Forsman
Production Engineering Advisor
EOG Resources – Vernal Operations

cc: Ted Kelly – Big Piney Office
Jim Schaefer – Denver Office
Denver file

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: EOG RESOURCES Operator Account Number: N 9550
Address: 600 17th St., Ste. 1000N
city Denver
state CO zip 80202 Phone Number: (303) 824-5590

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
43-047-39059	EAST CHAPITA 818-16		SWSE	16	9S	23E	Uintah
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
D	16707	18940	2/14/2008		3/12/2013		
Comments: 3/12/13							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
43-047-39151	EAST CHAPITA 57-16		NWNW	16	9S	23E	Uintah
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
D	16730	18940	3/4/2008		3/12/2013		
Comments: 3/12/13							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
43-047-39150	EAST CHAPITA 60-16		NENE	16	9S	23E	Uintah
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
D	16784	18940	4/5/2008		3/12/2013		
Comments: 3/12/13							

RECEIVED

MAR 11 2013

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

Vail Nazaro

Name (Please Print)

Vail Nazaro
Signature

Senior Regulatory Assistant

Title

3/8/2013

Date